

THE FIVE ORDERS
OF
ARCHITECTURE

THE CASTING OF SHADOWS

AND

THE FIRST PRINCIPLES OF CONSTRUCTION

BASED ON THE SYSTEM OF

VIGNOLA

SEVENTY-SIX PLATES, DRAWN AND ARRANGED BY

PIERRE ESQUIÉ

ARCHITECT OF THE FRENCH GOVERNMENT
FORMER MEMBER OF THE FRENCH ACADEMY AT ROME

CONCORDIA COLLEGE
LIBRARY
MOORHEAD, MINN.

BOSTON, MASS.

BATES & GUILD COMPANY

WITHDRAWN
FROM THE
CARL B. YLVISAKER LIBRARY
Concordia College, Moorhead, MN

PREFACE

A general formulation of the proportions of the classical orders is accepted as a valuable aid, if not an essential, to both the study and the practice of architecture. Many such systematic arrangements of the orders have been made, but none have been more widely or more continuously used than that of Vignola. In the present edition of this time-honored work M. Pierre Esquié has retained all of the features of former editions which are of especial value to architects of today, and has added new and important material, thus rendering it the most complete and useful edition so far issued.

The addition of the Greek orders in a consistent form with the Roman orders of Vignola is here made for the first time. The details of stone-jointing and of vaulting, in the drawings of the porticoes of the different orders, and the clearer and better arrangement of many of the plates, are points of superiority which can be readily appreciated.

The explanatory notes upon each plate have been carefully translated into English, and the definitions, measurements and references to figures, scattered over the plates, have been gathered together in a glossary with their English equivalents. It has not, however, seemed advisable to give exhaustive definitions, as the only purpose of the glossary is to enable the student to comprehend the plates and follow the explanatory notes; consequently only the restricted sense in which the terms are used has been considered. In the case of many of the terms devoted to construction (Plates LXVII. to LXXVI.) the English may not even be the equivalent of the French in any other respect than that both refer to the same architectural form or member in the particular applications of this work.

EXPLANATION OF PLATES

PLATE I.

EXPLANATORY PARALLEL OF THE FIVE ORDERS OF ARCHITECTURE ACCORDING TO VIGNOLA; AND THEIR RELATIVE PROPORTIONS TO EACH OTHER.

An order is the combination of architectural elements necessary to hold up the solids above an opening. When complete the order consists of an entablature, a column and a pedestal. The pedestal is not, however, indispensable.

Since the relative proportions of these elements must vary according to the materials employed, or the degree of richness desired, the resulting combinations have been resolved into five types, which have been called the Tuscan, the Doric, the Ionic, the Corinthian and the Composite orders. The proportions, which are here given according to Vignola, are far from absolute, but one should not forget that they are a mean, and that by differing from them too much and without a reason there is risk even of absurdity.

This plate shows the parallel of the five orders of architecture given by Vignola. The proportions of the orders one to another can be seen by the scale of heights, divided into thirty-two parts, one part being assumed as the module. The Tuscan, the Doric and the Ionic have the same relative proportions, shown by the lines AA — BB — CC; that is to say, for these three orders the pedestal is one-third and the entablature one-fourth the height of the column. It is only for the Corinthian and Composite orders that Vignola has thought it necessary to change this proportion. While keeping the entablature one-fourth the height of the column he has raised the pedestal one-third of a module, thus making these two orders still more elegant. This makes the pedestal 7 modules high, instead of $6\frac{1}{2}$ as in the three previous orders. The module is divided into 12 parts for the first two orders and into 18 parts for the last three.

PLATE II.

DRAWING MOULDINGS.

The ability to draw straight lines and tangential curves with accuracy is indispensable if one would produce curves which have a continuous sweep. This operation (called in French *raccordement*) consists in so joining lines as not to leave any break between them. The process is employed in architecture in a multitude of ways, and especially in the drawing of mouldings.

Mouldings are divided into *simple* and *compound*. The principal simple mouldings are: the Cavetto, the Quarter-round and the Torus. The principal compound mouldings are the Cyma-recta, the Cyma-reversa and the Scotia.

The cavetto, is, in profile, a concave quarter-circle, in which the projection is equal to the height. An examination of the three first figures of this plate will suffice to make clear the method of drawing it.

The cyma-recta is a sinuous moulding, the upper part of which is concave, and the projection of which equals the height. It is drawn as follows: The projection AC being taken equal to the height AB, the points B and C are joined by a straight line, which is divided in two equal parts at the point D. Upon the sides DB, DC of this line, construct, one inside and one outside, two equilateral triangles, which determine the centres, O, O' of the circular arcs CDB, which form the cyma-recta.

The cyma-reversa is a moulding formed by two continuous circular arcs; the method of drawing will be made clear by examination of the diagram.

The scotia is a hollow moulding placed ordinarily between two vertical supporting members. It is drawn as follows: Given the parallels mt, XT and their tangent points T and t, and any point in mt, as n. Erect the perpendiculars tO', Ti, nX. Take $Xy = \frac{1}{3} Xn$, and from y draw yi parallel to mt to intersect Ti at i. With i as centre describe the quarter circle TK. Extend io = $\frac{1}{3}$ Ki. From o as centre describe the arc KH equal to one-half the arc TK. Produce Ho to Z, making oZ = $\frac{1}{4}$ oH. Make tQ = HZ and join Q and Z, and at the centre of this line M erect the perpendicular MO'. The point Z will be the centre for HL and O' for Lt.

PLATE III.

TUSCAN INTERCOLUMNIATION.

FIGURE 1. Elevation of the Tuscan Intercolumniation.

FIGURE 2. Section of the Tuscan Portico.

FIGURE 3. Plan of the Tuscan Portico.

The distance from one column to another is called the Intercolumniation. The intercolumniation should never be so great that the stability of the structure, either real or apparent, may suffer, nor so narrow as to prevent the access of light, or easy passage between the columns. In a colonnade the intervals should be equal, unless there may be necessity to open a wider passage in the middle for a principal entrance.

Vignola, having found nothing in the buildings of antiquity which could serve as the type of the Tuscan order, has made it conform to the rules of Vitruvius, who says that the height of the column is seven times its diameter, including the capital and base, that is to say 14 modules.

To draw the Tuscan intercolumniation divide the whole height of the order into 5 parts, the upper part being taken for the entablature and the four remaining for the column. Divide these four parts into 14, and the $\frac{1}{4}$ part will be the length of the module, from which make a scale. Next draw perpendicular lines $6\frac{1}{2}$ modules apart for the axes of the two columns. Reserving one module for the base and one for the capital, there remain 12 modules for the shaft, which is cylindrical for one-third of its height, and diminishes progressively for the remainder of the height as far as the astragal, where it is 1 module and 7 parts in diameter. The diminution of the column will be explained in a later plate.

PLATE IV.

THE TUSCAN PORTICO WITHOUT PEDESTAL.

Arches are more substantial than stone lintels and consequently arcaded porticos are used for the lower stories of buildings. This plate shows the elevation of a Tuscan portico without pedestal. It will be seen that the columns are engaged in the pier $\frac{1}{2}$ of a diameter, or 9 parts.

Divide the whole height of the order, as for the intercolumniation, into five equal parts, of which four are to be given to the column and one to the entablature. Then divide the height of the column into fourteen parts to obtain the module, or half diameter, after which erect two perpendiculars $9\frac{1}{2}$ modules apart for the axes of the columns. Draw the piers, $1\frac{1}{2}$ modules on each side of these perpendiculars. Mark off one module from the top upon the middle line of the arch for the height of the keystone. Measure down again upon this line 3 modules and 3 parts, which is half the width of the *arcade**; this will at the same time give the centre of the arch and the height of the impost. Notice that this *arcade* is just twice as high as it is wide, the proportions generally adopted by Vignola.

The relation between the width of the opening and that of the pier may vary. The construction may appear heavy, when the width of the pier equals that of the opening; on the other hand it may seem thin and delicate, when the width of the opening is three times that of the pier. The most desirable proportion is that in which the pier is half the width of the opening.

It has been thought desirable to give an example of the method of laying out the stone-cutting of a portico, although this should vary in design according to the actual dimensions and the materials of which the portico is built.

* The French term *arcade* is used in this work for an opening in masonry composed of an arch supported either by columns or piers. It has no exact English equivalent; the French form is therefore used in the translation.

PLATE V.

THE TUSCAN PORTICO WITH PEDESTAL.

The order with pedestals is generally used in porticos which are to be closed with a balustrade, in order to avoid

the accidental meeting of the railing of the balustrade and the columns.

To draw the Tuscan portico with pedestal it is necessary first to divide the whole height into nineteen equal parts, of which three are given to the entablature, twelve to the column, and four to the pedestal.

To obtain the module the height of the column is divided into fourteen parts, as in the portico without pedestal. With this module as a unit it will be easy to draw the portico as indicated in the plate.

It will be seen that in this case again the arch is twice as high as it is wide.

Although the measurements given by Vignola for the thickness of the piers make them of satisfactory proportion, it is nevertheless allowable to modify these proportions, if need be, adapting them in such a way as to support properly the weight placed upon them.

It will be seen that in this portico also the columns are engaged one-third of their diameter.

Together with the elevations of the Tuscan porticos, in both cases, the sections taken on the axis of the *arcade* have been shown, in order to make clear what is meant by a section. They will be repeated for the other orders. The interiors of these porticos should be adapted to the construction and to the materials employed. The Tuscan order being simple it will be well to treat the interior with like simplicity.

PLATE VI.

THE TUSCAN PEDESTAL AND BASE.

- FIGURE 1. Elevation of the Base and the Pedestal.
- FIGURE 2. Section of the Base and the Pedestal.
- FIGURE 3. Profile of the Base and the Pedestal.
- FIGURE 4. Plan of the Base and of the Cornice of the Pedestal.
- FIGURE 5. Plan of the Base of the Pedestal.

The Tuscan order is simple and rude, its principal characteristic is force. It should have no applied ornament unless rustication or some like decoration be used.

Although it is not customary to use a pedestal in the Tuscan order, Vignola has thought it necessary to show one to carry out the plan he has adopted for his treatise upon the five orders. He makes the pedestal $\frac{1}{3}$ the height of the column, which gives it 4 modules and 8 parts, including the base and the cornice, to each of which $\frac{1}{2}$ module is allowed. The die is $3\frac{1}{2}$ modules high, and equal in width to the plinth of the base of the column, which is 2 modules and 9 parts. The height of the base of the column is 1 module, divided in two equal parts, one for the plinth and one for the torus with its cincture, the height of the latter being 1 part. In this order the cincture or listel C is not included in the height of the shaft.

It should be noted that the module is determined by the diameter of the column taken just above the base, which is always 2 modules. The module is divided into 12 parts, or minutes, for the Tuscan order.

When the pedestal is continued it is called a stylobate.

NAMES OF THE MEMBERS COMPOSING THE BASE AND THE PEDESTAL OF THE

TUSCAN ORDER

A. Shaft of the column.	} Base of the column.
B. Congé.	
C. Listel or cincture.	
D. Torus.	
E. Plinth of the base.	
F. Listel or Reglet.	} Cornice of the pedestal.
G. Cyma reversa.	
H. Die.	
I. Congé	} Base of the pedestal.
K. Fillet or listel.	
L. Plinth of the Pedestal.	

NOTE.—By an error of the engraver the semi-diameter of the torus and the plinth of the base is figured in the plan (Figs. 3 and 4), as 1 module $5\frac{1}{2}$ parts. This should be 1 module $4\frac{1}{2}$ parts, as will be seen by comparison with the other figures.

PLATE VII.

ENTABLATURE AND CAPITAL OF THE
TUSCAN ORDER.

- FIGURE . Elevation of the Tuscan Capital and Entablature.
FIGURE . Section of the Capital and Entablature.
FIGURE . Impost of the Tuscan Arcade without Pedestal.
FIGURE . Impost of the Tuscan Arcade with Pedestal.

The Tuscan entablature is one-quarter the height of the column, which consequently makes it $3\frac{1}{2}$ modules, of which 1 module is given to the architrave, 1 module and 2 parts to the frieze, and the remainder to the cornice. In the section of this cornice the undercutting of the corona can be seen, which forms a drip to protect the rest of the entablature from water which might run down. The height of the capital is 1 module. The shaft of the column under the astragal is diminished 5 parts, or $2\frac{1}{2}$ parts on each side.

At the bottom of the plate is given the plan of the capital and entablature. It shows clearly the return of the cornice at the angle.

The figure at the left of the plate, which gives the impost and archivolt of the Tuscan arch with pedestal (the lower of the two figures), has not been made according to the measurements given by Vignola. It was thought necessary to correct Vignola's proportions in certain parts to give them more grace.

The entablature is divided into three parts, the architrave, the frieze and the cornice.

The architrave is the lower part of the entablature, that which rests immediately upon the capital of the column and serves to carry the members above it.

The frieze is the space which separates the architrave from the cornice.

The purpose of the cornice is to protect the walls against the action of rain-water.

The purpose of the capital is to carry the architrave and to give a greater bearing for the entablature upon the column.

NAMES OF THE MOULDINGS OF THE ENTABLATURE AND CAPITAL OF THE
TUSCAN ORDER.

A. Quarter-round.	} Cornice.
B. Baguette, or astragal.	
C. Fillet.	
D. Corona.	
E. Listels.	
F. Cyma reversa.	

G. Frieze.	} Architrave.
H. Listel.	
I. Fascia of the architrave.	
K. Listel of the abacus.	} Capital.
L. Fascia of the abacus.	
M. Quarter-round or echinus.	
N. Fillet or annulet.	} Shaft.
O. Neck.	
P. Astragal.	
Q. Fillet or cincture.	} Impost.
R. Shaft.	
S. Fillet.	
T. Fascia of impost.	} Impost.
U. Second fascia of impost.	
Y. Fascial of archivolt.	

PLATE VIII.

TEMPLE OF THE TUSCAN ORDER.

- FIGURE 1. Elevation of the Temple.
FIGURE 2. Plan.
FIGURE 3. Section.

There are given in this plate the principal elevation, the plan and the longitudinal section of a Tuscan temple, with antæ. The middle of the wall which separates the portico from the interior is occupied by a doorway ornamented with an architrave. The details of the pediment will be found in the following plate.

A. Courses of stonework.	M. Portico.
B. Door-jamb or architrave.	N. Cella.
C. Plinth.	O. Steps.
D. Antæ.	

PLATE IX.

DRAWING AND STUDY OF PEDIMENTS OF
THE TUSCAN ORDER.

- FIGURE 1. Elevation of straight and curved Pediments.
FIGURE 2. Side elevation of Pediments.
FIGURE 3. Section.
FIGURE 4. Method of drawing straight Pediments.
FIGURE 5. Method of drawing curved Pediments.

A pediment is nothing more than a gable, ornamented or concealed; it is not then properly used unless the gable exists. It is rather difficult to establish what are to be accepted as the correct proportions for pediments because of the variation in antique buildings. The process here given is the one suggested by Serlio, which seems to have been very successful for the Tuscan and Doric orders. An examination of the figures will suffice to make clear the different methods employed in drawing.

PLATE X.

DORIC INTERCOLUMNIATION ACCORDING
TO VIGNOLA.

To draw the Doric intercolumniation it is necessary to divide the whole height into five parts, one for the entablature and the four remaining for the column; or, as Vignola says, divide the height into twenty parts, one of which will

be the module. This module is divided, as in the Tuscan order, into 12 parts. The column will have 16 modules or eight times its greatest diameter. One module is given to the base, 1 to the capital, and 14 remain for the height of the shaft. The entablature has 4 modules, of which 1 is given to the architrave, $1\frac{1}{2}$ to the frieze and $1\frac{1}{2}$ to the cornice. All of these parts combined will make the height of the whole order, 20 modules.

In the frieze the triglyphs are always in line with the axes of the columns and are 1 module in width. The metopes are square and measure $1\frac{1}{2}$ modules. They can be enriched with various ornaments, such as heads of oxen, armor, *patera*, etc. The Doric intercolumniation is always determined by the number of the triglyphs. The column has 20 flutes. The contour of the shaft is drawn as in the Tuscan order.

PLATE XI.

DORIC PORTICO WITHOUT PEDESTAL.

To construct this Doric portico without pedestal, it is always necessary to divide the height into five parts, of which one is given to the entablature and four to the column; or else to divide the whole height into twenty parts, of which one will be the module. Mark off 10 modules for the distance from axis to axis, of which take 7 modules between the piers for the width of the arch, and allow 3 modules for the width of the piers. This will result in a proper division of the triglyphs and metopes.

The arch will be twice as high as it is wide. It should be noted that the column should project $\frac{1}{2}$ module more than half its diameter, in order that the projection of the imposts, which is also $\frac{1}{2}$ module, shall not protrude beyond the plane of the diameter of the column, which is parallel with the face of the pier. This is done in order that the projection of the imposts may not intersect disagreeably with the columns.

PLATE XII.

DORIC PORTICO WITH PEDESTAL.

The Doric portico with pedestal is generally employed for large openings; examples of it are found in the façades of city gates and in public buildings.

It is to be noted that the columns in this arrangement of the order are almost entirely accessory and decorative, on account of their wide spacing.

It is necessary, says Vignola, if it is desired to erect a portico or a loggia decorated with the Doric order with pedestals, to divide the whole height into $25\frac{1}{2}$ parts and to make one of these parts the module. Then make the distance from one pier to the next (in the clear) 10 modules, and the width of each pier 5 modules. These measurements are necessary in order to obtain the proper distribution of the triglyphs and metopes in the entablature. The arcade will consequently be just twice as high as it is wide, that is, 20 modules in height.

Although the measurement of $2\frac{1}{2}$ modules is given in the figure, the thickness of the pier should be left to the archi-

tect who employs this arrangement of the order, for the piers should have a thickness properly proportioned to the weight they are required to support and to the thrust of the vaults.

The details of this exercise are given in the following plates.

PLATE XIII.

PEDESTAL AND BASE OF THE DORIC ORDER.

- FIGURE 1. Elevation of the Pedestal and Base of the Doric Order.
 FIGURE 2. Section of the Pedestal and Base.
 FIGURE 3. Profile of the Pedestal and Base.
 FIGURE 4. Plan of the Base.
 FIGURE E. Flute drawn with an equilateral triangle.
 FIGURE F. Flute drawn with a semicircle.

As in the Tuscan order, the module is here divided into 12 parts or minutes. The pedestal is 5 modules and 4 parts high, or $\frac{1}{3}$ the height of the column; the base of the column has 1 module, and a *baguette* or astragal, measuring 1 part in height, is placed above the torus, reducing the height of the latter by this amount, which renders this base more elegant and lighter than that of the Tuscan order. Doric columns can be made either with or without flutes. To obtain the flutes the circumference of the column is divided into 20 equal parts. The chords of these 20 arcs serve as the bases of as many equilateral triangles, of which, in each case, the apex is the centre from which a portion of a circle can be described to form the flute, as in Fig. E. If it is desired to make the flutes more pronounced (Fig. F.), join the points b c by a straight line, elevate the perpendicular a d, and describe the semicircle b d c, and the point d will be the centre from which an arc can be described giving the deeper flute.

The section of the pedestal shows the undercutting of the corona, or drip, the purpose of which is to stop the running down of rain-water, which otherwise would quickly deteriorate the other parts of the pedestal.

NAMES OF THE MOULDING COMPOSING THE BASE AND THE PEDESTAL OF THE DORIC ORDER.

a. Shaft.	A. Base of the column.
b. Lower congé of shaft.	
c. Annulet, or cincture, or fillet.	
d. Astragal, or baguette, or baton.	
e. Torus.	B. Cornice of the pedestal.
f. Plinth of base.	
g. Fillet or listel.	
h. Quarter-round or echinus.	
i. Corona.	C. Die of the pedestal.
j. Drip.	
k. Cyma reversa.	
l. Die.	
m. Congé.	Base of the pedestal.
n. Astragal or baguette.	
o. Inverted cyma reversa.	
p. Upper plinth.	
q. Lower plinth.	

PLATE XIV.

ENTABLATURE AND CAPITAL OF THE
DENTICULAR DORIC ORDER.

- FIGURE 1. Elevation of the Entablature and Capital of the Denticular Doric Order.
 FIGURE 2. Section of the Entablature and Capital.
 FIGURE 3. Plan of the Capital.
 FIGURE 4. Impost and Archivolt of the *Arcade* without Pedestal.
 FIGURE 5. Impost and Archivolt of the *Arcade* with Pedestal.
 FIGURE 6. Section of the Cornice upon the line AB.
 FIGURE 7. Plan of the Cornice and of the Denticular Frieze.

This plate gives the different details of the Denticular Doric order.

The entablature is one-fourth the height of the column, and the capital is 1 module high. The triglyphs are each 1 module in width; the incised spaces in them are called channels, the object of which is to accentuate the function of the triglyph, which is to support the cornice, the metope being only a filling in. The metopes should always be square and may be ornamented with heads of animals, trophies of war, etc.

This order is usually employed in the lower stories of buildings.

- | | |
|--------------------------|-----------------------------|
| A. Cavetto. | D. Triglyphs with channels. |
| B. Denticils. | E. Guttæ. |
| C. Capital of triglyphs. | H. Metope. |

PLATE XV.

ENTABLATURE AND CAPITAL OF THE
MUTULAR DORIC ORDER.

- FIGURE 1. Elevation of the Entablature and Capital of the Mutular Doric Order.
 FIGURE 2. Section of the Entablature and Capital.
 FIGURE 3. Plan of the Capital.
 FIGURE 4. Section, following the line AB, of the Cornice.
 FIGURE 5. Plan of the Cornice and of the Frieze.

This order is obviously different from the preceding one. In the cornice the cavetto is replaced by a cyma-resta and the cyma-reversa by a quarter-round. The mutules, which are not used in the Denticular Doric, give a greater solidity to the cornice and contribute to its enrichment. The architrave has two faces instead of one, and the mouldings of the capital are ornamented.

The Mutular Doric order, richer than the Denticular, is the one most used both in public and private buildings.

At the left of Figure 4. Detail of a gutta, or drop, in the soffit of the mutule. Detail of the guttæ, or drops, in the architrave under the triglyph.

- A. Cymatium, or cyma recta.
 B. Mutule, with guttæ.
 C. Second fascia of the architrave.
 D. First fascia of the architrave.

PLATE XVI.

TEMPLE OF THE DORIC ORDER.

- FIGURE 1. Elevation of a Temple of the Doric Order.
 FIGURE 2. Plan of the front portion of the Temple.
 FIGURE 3. Section upon the axis of the Doorway.

This plate represents a Mutular Doric portico of three intercolumniations. The intercolumniation is determined by the number of triglyphs. The maximum of three intermediate triglyphs should never be exceeded. See the following plate for the method of drawing the pediment.

- A. Courses of masonry.
 B. Cornice of the doorway.
 C. Frieze of the doorway.
 D. Door-jamb or architrave.
 E. Plinth.

PLATE XVII.

DRAWING AND STUDY OF PEDIMENTS OF
THE DORIC ORDER.

The method of drawing used in this plate is based upon the same principles as those given for the Tuscan order. An examination of the plate will show clearly to the student the way to draw the inclined mouldings. Figure 1 shows the pediment of the Denticular Doric; Figs. 2 and 3 show the junction of the horizontal and inclined mouldings. It is to be noted that the cavetto has a small horizontal portion which it is impossible to avoid. Figure 4 represents the pediment of the Mutular Doric, and Figs. 5 and 6 the joining of the inclined and horizontal mouldings, as well as the exact form of the cyma-recta at the apex of the pediment.

PLATE XVIII.

THE IONIC INTERCOLUMNIATION.

The Ionic intercolumniation is laid out in the same way as that of the Tuscan and Doric, by dividing the whole height of the order into five equal parts, of which the four lower make the height of the column. This height (of the column) is divided into eighteen parts, which will give the module. The module of this order is divided into 18 parts, or minutes, to measure the various mouldings, this division being necessary because of the great number of mouldings, which are also more delicate than in the two preceding orders.

The Ionic order is frequently employed for interior treatment on account of its elegance, or on the exterior in the upper stories of buildings. The ancients used it in numerous temples, a good example of which is the temple of Fortuna Virilis at Rome.

It should be noted that the angle capital A returns at the angle in such a way as to present volutes on both faces.

PLATE XIX.

IONIC PORTICO WITHOUT PEDESTAL.

In order to draw the Ionic portico without pedestal, divide the height, as in the preceding plate, into five equal parts, the upper part for the entablature and the four lower for the column. The *arcade* is always twice as high as wide.

The columns are engaged in the pier $\frac{2}{3}$ of a module.

The Ionic portico can be used to advantage in the second story of courtyards of palaces or of public buildings which call for a rather ornate treatment.

Students will do well to practise drawing this portico owing to the difficulty of drawing the volutes on a small scale.

NOTE. — In the note upon this plate it is stated that the columns are engaged one-third of a module; this is an engraver's error and should be one-third of a diameter.

PLATE XX.

IONIC PORTICO WITH PEDESTAL.

The Ionic portico with pedestal is used as a rule in large buildings, and especially for the principal story. The relation of its parts, and its individual forms, are more elegant than those of the two preceding orders, the character of which is more that of strength and solidity.

To draw the Ionic portico with pedestal it is necessary to divide the whole height into $28\frac{1}{2}$ parts of modules.

The pedestal, including its base and cornice, should be 6 modules in height, that is, one-third the height of the column. There will be left, therefore, $4\frac{1}{2}$ modules for the height of the entablature, according to the rule adopted by Vignola. The width of the pier is 4 modules and the *arcade* is always twice as high as it is wide.

The section, made upon the axis of the *arcade*, shows a barrel vault with rib arches at right angles to the columns and the penetrations.

PLATE XXI.

PEDESTAL AND BASE OF THE IONIC ORDER.

FIGURE 1. Elevation of the Pedestal and of the Base of the Ionic Order.

FIGURE 2. Section of the Pedestal and of the Base.

FIGURE 3. Profile of the Pedestal and of the Base.

FIGURE 4. Plan of the Base.

The Ionic order occupies, by reason of its form and decoration, the position of mean between the Doric on the one hand, which represents strength and solidity, and the Corinthian on the other, which is the complete type of elegance and richness. The refined taste of the Greeks required something between these two systems, the one simple and severe, and the other more graceful, richer and more noble.

The Ionic pedestal which is given in this plate is one-third the height of the column, that is, 6 modules. Its base

and cornice are each $\frac{1}{2}$ module high, the die 5 modules, including the two fillets. The base of the column given here is that of Vignola. An example will be given later of the Attic base, employed by the ancients. This base is 1 module high, not including the listel or cincture. The shaft of the column is ornamented with 24 semicircular flutes, which terminate squarely at the beginning of the congé. The width of the listel between the flutes is $\frac{2}{3}$ of that of the flutes.

- | | |
|----------------------------------|----------------------------|
| A. Semicircular flute. | E. Torus. |
| B. Side of the flute, or listel. | F. Upper scotia. |
| C. Congé. | G. Baguettes or astragals. |
| D. Listel. | H. Lower Scotia. |

PLATE XXII.

ENTABLATURE AND CAPITAL OF THE IONIC ORDER WITH CUSHION.

FIGURE 1. Elevation of the Entablature and Capital of the Ionic Order.

FIGURE 2. Section of the Entablature and Capital.

FIGURE 3. Profile of the Capital.

FIGURE 4. Plan of the Angle Capital.

This plate represents at large scale the details of the entablature and capital of the Ionic order, as well as the imposts of this order. The capital given is that of an angle column, based upon the proportions of the Temple of Fortuna Virilis at Rome. By reason of this special arrangement the capital is symmetrical when seen diagonally. The other capitals of a series are made up of two parts similar to A, Fig. 1.

At the left of Figure 1 (upper drawing). Impost and archivolt of the *arcade* without pedestal. (Lower drawing.) Impost and archivolt of the *arcade* with pedestal.

PLATE XXIII.

STUDY OF THE VOLUTE AND CUSHION OF THE IONIC CAPITAL.

FIGURE 1. Face of the Ionic Capital.

FIGURE 2. Plan of the Capital.

FIGURE 3. Profile of the Capital showing the detail of the Cushion.

FIGURE 4. Second method of drawing the Volute.

Two methods of drawing the volute are given. For the first see Fig. 1.

Having drawn the cathetus* of this first volute, and having prolonged the upper line of the astragal which will intersect the cathetus at right angles in the centre of the eye of the volute at a distance of 1 module from the axis of the column, inscribe a square in the eye of the volute as shown in the detail, Fig. A. Then draw two diagonals through the centre of the eye of the volute, perpendicular to the sides of the square, and divide the distance from the centre to the side of the square into three equal parts. This will give twelve points which will serve as centres for portions of circles, which together will make up the three revolutions

* The cathetus is the vertical line passing through the centre of the eye of the volute.

of the spiral of the volute. To describe this spiral begin by taking the point 1 (Fig. A.) as a centre, and with the radius 1B describe a quarter circle from B, terminating at the horizontal line 1 2; then with the point 2 as centre, and radius the distance from 2 to the extremity of the quarter circle just described, draw a second quarter circle, and repeating this operation as far as the point 12 the outer arris of the listel of the volute will be obtained. To obtain the other arris, divide each of the three parts of the semi-diameters of the square into four equal parts and from each of these divisions next adjoining the successive centres for the first spiral describe twelve other quarter circles which will give the other spiral of the listel. The dotted lines passing through the centre point indicate the terminations of the quarter circles.

Second Method. To construct the volute by the method shown at the bottom of this plate, draw the line called the cathetus 16 parts of a module in length, 9 parts above and 7 parts below, and at the centre thus obtained draw the eye of the volute and divide its circumference in eight parts by diagonals, as shown. Then construct the auxiliary triangle BAC, of which the side BA will be 9 parts and AC 7 parts of a module. What remains will be easily understood from the drawing, the distances A1, A2, etc., being marked off from the centre of the eye on the eight diagonals. To draw the contour join the points 1 and 2 by a straight line, and at its centre erect a perpendicular. With 1 as a centre and the distance 1A as radius, cut this perpendicular, which will give the centre for the arc of a circle which will join 1 and 2. Then repeat the same operation for the remainder of the spiral. The points on the eight diagonals can be joined by a curve drawn free-hand without using compasses. For the width of the listel mark off on the eight diagonals the corresponding distances on the line A'B', and follow the same method as above.

The cushions, Figs. 2 and 3, should be drawn free-hand in order to give them a more graceful form; nevertheless, in order to facilitate the drawing, a method of constructing them mechanically is given.

- AB. Perpendicular line called the cathetus.
A. Eye of the volute with detail of the points of centre.
D. Eggs. E. Shell of eggs. F. Darts. G. Pods.
H. Profile of the cushion from the side.
I. Section of the volute upon the line AB.

NOTE.—It is to be regretted that the ornaments of eggs and darts and pods upon the echinus of the capital, shown in Fig. 1, are not accurately drawn. If these ornaments be drawn upon the plan (Fig. 2) and produced point by point from plan to elevation, the inaccuracy will quickly be made evident.

PLATE XXIV.

ENTABLATURE AND CAPITAL OF THE IONIC ORDER WITH FOUR VOLUTES.

- FIGURE 1. Entablature and Capital with four Volutes.
FIGURE 2. Section of the Entablature and Capital.
FIGURE 3. Base.
FIGURE 4. Section of the Base.
FIGURE 5. Plan of the Capital with four Volutes.

Because of the difficulty experienced in using satisfactorily the Ionic capital at the angle of a building, the Ionic

order with four volutes without a cushion is sometimes used. As Vignola has not given an example of this disposition of the order, that adopted by Scamozzi is here shown.

PLATE XXV.

THE TEMPLE OF FORTUNA VIRILIS AT ROME.

In order to complete the explanation of the Ionic order an example is given of a temple built by the Romans, dedicated to Fortuna Virilis. It is the most beautiful example of this order which has been preserved to us in so complete condition. It seems advisable to place it before beginners in order to persuade them from the beginning of their studies of the art of architecture never to depart from good traditions and to familiarize themselves thoroughly with the beauties of antiquity.

PLATE XXVI.

CORINTHIAN INTERCOLUMNIATION.

To draw the Corinthian intercolumniation divide the whole height into 25 parts, one of which will be the module, which is divided in 18 parts or minutes, as in the Ionic order. Vignola establishes the distance between the columns at $4\frac{1}{2}$ modules, in order to arrange the spacing of the modillions in the cornice so that one may always be in line with the axis of the column.

This order, distinguished above all the others by its magnificence, should be employed principally for great monuments, such as temples and palaces.

NOTE.—By a mistake of the engraver the distance between the columns is given in the note as $4\frac{1}{2}$ instead of $4\frac{3}{4}$ modules.

PLATE XXVII.

CORINTHIAN PORTICO WITHOUT PEDESTAL.

This arrangement of the portico without pedestal is obtained by dividing the whole height into 25 parts, one of which will be the module. The explanations given in the preceding plates are not repeated here, the proportions of the height of the column and entablature being the same.

The width of the arcade is 9 modules and its height 18, or double the width.

Few examples of the Corinthian portico without pedestal are found in execution. It is advisable moreover, not to use this arrangement of the order without some kind of sub-base under the piers, in order that the base, which is formed of delicate mouldings, may not be placed directly upon the ground, at the risk of being quickly damaged.

The section shows the intersection of the arch with a barrel vault, the width of which may vary according to circumstances.

NOTE.—By a mistake of the engraver the height of the arcade is figured in the section 8 instead of 18 modules.

PLATE XXVIII.

CORINTHIAN PORTICO WITH PEDESTAL.

To draw this Corinthian portico with pedestal, divide the whole height in 32 parts, of which one will be the module, and give 12 modules to the width of the *arcade* and 16 from axis to axis of the columns, making the piers 4 modules in width.

This portico and that of the Composite order are the only ones in which Vignola departs from the uniform proportion of the *arcade*, the height twice the width. This is done to give the order greater delicacy and grace, and also to give greater height to the keystone, thereby making the latter more serviceable.

A section through the axis of the *arcade* is given in order to make clear the relation of the exterior to the interior when a groined vault is used.

The thickness of the pier may vary according to the weight and thrust which it may have to support.

This arrangement of the order is employed in the most important class of monuments and in the upper stories of buildings.

PLATE XXIX.

PEDESTAL AND BASE OF THE CORINTHIAN ORDER.

- FIGURE 1. Elevation of the Base and of the Pedestal of the Corinthian Order.
 FIGURE 2. Section of the Base and of the Pedestal.
 FIGURE 3. Profile of the Base and of the Pedestal.

The module of the Corinthian order is divided into 18 parts or minutes. In this order Vignola makes an exception to the general rule that the pedestal should be one-third of the height of the column. This is done to give it grace to correspond with the rest of the order. Vignola advises making it 7 modules in height; thus the die of the pedestal is twice as high as wide, or the equivalent of two superposed squares. The plinth of the base of the pedestal may be heightened, giving it 8 parts instead of 4.

The base of the column shown in the plate is that given by Vignola. The ancients sometimes used instead the so-called Attic base, the mouldings of which are more beautifully proportioned.

PLATE XXX.

ENTABLATURE AND CAPITAL OF THE CORINTHIAN ORDER.

- FIGURE 1. Elevation of the Corinthian Entablature and Capital.
 FIGURE 2. Section of the Entablature and Capital.
 FIGURE 3. Section of the Cornice.
 FIGURE 4. Plan of the Cornice.
 FIGURE 5. Impost and Archivolt of the *Arcade* without Pedestal.
 FIGURE 6. Impost and Archivolt of the *Arcade* with Pedestal.

The height of the entablature is divided into 10 parts, of which 3 are given to the architrave, 3 to the frieze and 4 to the cornice. Above each modillion on the cyma is placed

a decorative motive or lion's head. In ancient buildings these were rain-water outlets; but in modern buildings they are only used for overflows.

PLATE XXXI.

STUDY OF THE CORINTHIAN CAPITAL.

- FIGURE 1. Diagonal projection of the Corinthian Capital.
 FIGURE 2. Plan, looking up, of the Capital.
 FIGURE 3. Elevation of the Corinthian Pilaster Capital.
 FIGURE 4. Plan of the Pilaster Capital.
 FIGURE 5. Profile of the Keystone of the Arch.
 FIGURE 6. Elevation of the Keystone of the Arch.

The Corinthian capital is ornamented by two rows of leaves, of the same height, and placed so that those of the upper row alternate with those of the lower. From between the leaves of the upper row spring the cauliculi from which start the volutes, terminating the capital. Upon the volutes is placed the abacus, which is composed of three members, the cymatium, the listel and the fascia of the abacus.

Vignola makes the Corinthian capital 2 modules and 6 parts high, of which 2 modules are for the vase and 6 parts for the abacus. All the other dimensions are indicated on the plate, and by carefully comparing the plan and profile they can be easily understood.

In Figures 3 and 4 are given the elevation and plan of the Corinthian pilaster capital. This pilaster is used either separately or behind columns, or upon the angles of buildings. The heights of the leaves and of the members of the mouldings are the same as in the capital of the column, but while the shaft of the column is 30 parts in diameter just below the capital, that of the pilaster is 34. The shaft of the column has 24 flutes and the pilaster has 7 upon its face.

- A. Cymatium. B. Fascia of the abacus. C. Volute.
 D. Leaf of the cauliculus. E. Larger leaf.
 F. Smaller leaf. G. Rose.

PLATE XXXII.

CORINTHIAN PEDIMENT.

In a pediment the triangular space inclosed by the three cornices is called the tympanum. It was in this space that the ancients placed figures, by means of which it has been possible to identify beyond question so many temples. The Corinthian temples, on account of the richness of the order, almost always bore this kind of decoration. Sometimes also, figures or other motives, forming a silhouette, were placed above these pediments, at the angles or at the apex.

At the right of plate: Section upon the line AB. At the left bottom corner: Profile of modillion and face of modillion.

PLATE XXXIII.

CORINTHIAN TEMPLE.

This plate gives an example of a hexastyle temple of the Corinthian order. It should be noted that the scales given are in metres and not in modules, in order to give a conception of the actual proportions.

PLATE XXXIV.

COMPOSITE INTERCOLUMNIATION.

To draw the Composite intercolumniation the same method is employed as that which has already served for the Corinthian order. It is necessary, however, always to give the shaft an entasis* of $\frac{1}{2}$ part at a point one-third the way up, and to diminish it progressively from this point to the astragal.

* See Plate XLIV.

PLATE XXXV.

COMPOSITE PORTICO WITHOUT PEDESTAL.

This portico is employed for the same class of structures as that of the Corinthian order. It is drawn in the same way, by dividing the whole height into five parts, the upper part for the entablature and the four others for the column. The *arcade* is exactly twice as high as it is wide.

In the section the interior is assumed to be barrel-vaulted in such a way as to avoid the penetrations of the arches.

PLATE XXXVI.

COMPOSITE PORTICO WITH PEDESTAL.

This portico can be used for the façades of palaces, as well as in galleries and in great halls, and for all places where it is desirable to decorate, architecturally, with great richness.

For explanation see Plate XXVIII., upon the Corinthian portico with pedestal.

The section shows a domical vault with pendentives.

PLATE XXXVII.

PEDESTAL AND BASE OF THE COMPOSITE ORDER.

- FIGURE 1. Elevation of the Pedestal and of the Base of the Composite Order.
FIGURE 2. Section.
FIGURE 3. Profile.

The proportions of the pedestal and base of the Composite order are the same as those of the Corinthian, the only difference being in the mouldings of the cyma and the base of the pedestal. Vignola did not ornament the mouldings of this pedestal, but it is not necessary to regard this as an absolute rule, as the order is a combination of the Ionic and Corinthian orders.

The shaft of the column, like the Corinthian, has 24 flutes. The width of the listels between the flutes is $\frac{2}{3}$ of the width of the flute.

PLATE XXXVIII.

ENTABLATURE AND CAPITAL OF THE COMPOSITE ORDER.

- FIGURE 1. Elevation of the Composite Entablature and Capital.
FIGURE 2. Section of the Entablature and Capital.
FIGURE 3. Section of the Cornice.
FIGURE 4. Plan of the Cornice.
FIGURE 5. Impost of the Archivolt of the *Arcade* without Pedestal.
FIGURE 6. Impost of the Archivolt of the *Arcade* with Pedestal.

In the Composite order Vignola has departed from the rule given for the Corinthian order by not making a dentil come directly in line with the axis of the column. This irregularity is not important, as in the case of modillions, because the ornaments are not of sufficient size for the eye readily to perceive it.

PLATE XXXIX.

HALF OF THE UPPER PART OF THE COMPOSITE CAPITAL SEEN UPON THE ANGLE.

The Composite capital is drawn in the same way as the Corinthian, the only difference being in the volutes. This part only is given in order to better show the detail. The construction of the spiral of the volute is the same as that described in Plate XXIII. for the Ionic order.

PLATE XL.

ARCH OF TITUS AT ROME.

Section, Principal Elevation and Side Elevation.

The arch of Titus, of which a restoration is here given, will make it possible to judge of the manner in which the ancients employed the Composite order. This order can be used for monuments which do not require great severity of treatment.

PLATE XLI.

SUPERPOSITION OF THE ORDERS.

- FIGURE 1. Elevation of the two Orders superposed.
FIGURE 2. Section.
FIGURE 3. Plan.
FIGURE 4. Plan of one of the first-story Piers.

In this plate is given a simple example of the superposition of the Ionic above the Doric order, taken from the Theatre of Marcellus at Rome.

It is to be noted that the Ionic column is shorter than that of the Doric by the length of one module of the Doric order, or one-half a diameter.

PLATE XLII.

SUPERPOSITION OF THE ORDERS.

- FIGURE 1. Elevation.
 FIGURE 2. Section.
 FIGURE 3. Plan of the Lower Story.
 FIGURE 4. Plan of the Upper Story.

This example of the superposition of the Ionic order above the Doric is taken from the interior court of the Farnese Palace, Rome. Notice the disposition of the angle, a plan of which is given for both stories. The plan of the upper story is indicated in dotted lines on that of the lower story.

PLATE XLIII.

STUDY OF THE PROPORTIONS OF THE ORDERS.

- FIGURE 1. Elevation of the Portico of Octavia.
 FIGURE 2. Plan.
 FIGURE 3. Detail.

When two orders are juxtaposed the smaller is generally made two-thirds the height of the larger. It is well not to depart too far from this proportion, when it cannot be followed exactly. As an example, the Portico of Octavia at Rome, which follows this rule, is given.

PLATE XLIV.

MANNER OF FORMING THE PROFILE OF COLUMNS.

- FIGURE 1. Method for the Tuscan and the Doric. The Tuscan shaft tapers from a point one-third the way up.
 FIGURE 2. Method for the Ionic, the Corinthian and the Composite. The Corinthian shaft is swelled at one-third its height.
 FIGURE 3. Shaft of a twisted column.

The diminution or the entasis of columns can be obtained in several ways. The two methods which Vignola considered best are here given.

Figure 1. — Determine first the height and thickness of the column and the amount of diminution in the upper two-thirds. Then describe a semicircle on the diameter at one-third the height of the column, at the point where it begins to diminish, and divide the arc AB into as many parts as desired, the point B being the projection of B'. The remainder of the process will be made clear by examining the figure.

Figure 2. — The various given points being established as in Fig. 1, for the Tuscan and Doric columns, the diameter at one-third the height being in the present case 2 modules, $2\frac{2}{3}$ parts, produce the line PO indefinitely, and from M as a centre with the radius PQ, describe an arc cutting the axis in R, and draw the line MRO. From O draw as many lines

as it is desired to obtain points, in each case making the distance from the axis to the profile of the shaft the same; for example, making ST = PQ.

Figure 3. — If it is desired to make a twisted column, first draw one of the straight columns. Then draw the small cylinder, shown in plan at E, to determine the eccentricity of the axis of the column. Divide the circle in 8 equal parts and from these points draw four lines parallel with the cathetus or axis of the straight column. Divide the height of the column into 48 equal parts, and draw the spiral in the small cylinder in the centre of the column. From this centre carry out on the 48 diameters the corresponding dimensions of the straight column, line for line. It is to be noted that the numbers 1, 2, 3, 4 represent only one-half a revolution of the spiral, going up, because this first revolution begins at the centre. In all the rest follow the circumference of the little circle, except in the upper circumference which is the same as the lower one and ends at the centre.

NOTE. — The term entasis (French *renflement*) when applied to columns is properly used only for swelling; that is to say, for columns which increase in diameter from the base to a point, say, one-third the way up, and then diminish toward the top.

PLATE XLV.

PARALLEL OF BALUSTRADES.

- FIGURE 1. Tuscan Balustrade.
 FIGURE 2. Doric Balustrade.
 FIGURE 3. Ionic Balustrade.
 FIGURE 4. Corinthian Balustrade.

The balustrade is nothing more than a support or elbow-rest. Its height is sometimes a little more and sometimes a little less than a metre. It should be raised upon a plinth sufficiently to allow its base to be seen above the projection of the cornice when viewed in perspective. The pedestals limiting a balustrade should always be in proper relation, as to richness of ornamentation, to the order with which the balustrade is used. A balustrade should not be confounded with an attic, the former being always in scale with the human form, while the latter is proportioned to the scale of the building as a whole.

The four principal types of balustrade are given in this plate, the metre and not the module being taken as the unit of measure.

PLATE XLVI.

INTERCOLUMNIATION OF THE GREEK DORIC ORDER.

The various Greek temples of which the remains are known were all of different proportions. A drawing is given in this plate of a Doric order which follows very closely the Parthenon at Athens.

To find the module of this order, the desired height being given, divide the whole height in $14\frac{1}{2}$ parts, one of

which will be the module, 11 parts being given to the column and $3\frac{1}{2}$ to the entablature. Directions in detail for drawing this order are given in Plate XLVII.

It should be noted that, as in the other Doric orders previously given, the module is divided in 12 parts, and in order to give the measurements for the smaller details each of these parts is subdivided into 12 minutes.

PLATE XLVII.

ENTABLATURE AND CAPITAL OF THE GREEK DORIC ORDER.

- FIGURE 1. Elevation of the Entablature and Capital of the Greek Doric Order.
 FIGURE 2. Section of the Entablature and Capital.
 FIGURE 3. Section of the Cornice on the side.
 FIGURE 4. Side Elevation of the Cornice.
 FIGURE 5. Section of the Triglyph.
 FIGURE 6. Plan of the Shaft of the Column at its Base.

In this plate is given a drawing of an entablature and capital of the Greek Doric order, closely resembling that of the Parthenon at Athens. It should be noted that the column represented, which is the corner column, does not follow the usual rule, being 2 modules and 6 minutes in diameter at the base. The other columns should be exactly 2 modules in diameter. This difference arises from the fact that the column is slightly inclined inward to give greater stability. It should also be noted that the triglyph in the Greek orders is at the angle of the frieze and not upon the axis of the column, as in the Roman and Renaissance Doric. This arrangement is much more logical, the triglyphs being supports for the cornice and the metopes merely filling of the space between.

PLATE XLVIII.

INTERCOLUMNIATION OF THE GREEK IONIC ORDER.

To draw the Greek Ionic intercolumniation divide the whole height into $21\frac{1}{2}$ parts, one of which will be the module. Take 4 parts for the entablature and $17\frac{1}{2}$ for the column. The module will be divided into 18 parts, and, for the subdivisions, each part into 18 minutes. For detailed instructions, see Plate XLIX.

PLATE XLIX.

ENTABLATURE, CAPITAL AND BASE OF THE GREEK IONIC ORDER.

- FIGURE 1. Elevation of the Greek Ionic Entablature and Corner Capital.
 FIGURE 2. Section of the Entablature.
 FIGURE 3. Side Elevation of the Corner Capital.
 FIGURE 4. Plan of the Corner Capital.
 FIGURE 5. Capital and Base of the Greek Ionic Pilaster.

The Greek Ionic orders were far from being always the same, and upon the Acropolis at Athens alone a number of examples have been found. The order given in this plate

resembles that of the Erechtheium, the grace and richness of which are remarkable.

In order to give the dimensions of the different members of mouldings, which are very delicate, the module is divided into 18 parts and each of these parts into 18 minutes.

In these orders, which were extremely rich, the frieze was almost always decorated with bas-reliefs.

PLATE L.

INTERCOLUMNIATION OF THE GREEK CORINTHIAN ORDER.

But very few examples of the Greek Corinthian order are known. That which is given in this plate is derived from the building known as the Monument of Lysicrates at Athens.

To draw the Greek Corinthian intercolumniation, the height being given, divide this dimension into 27 equal parts, one of which will be the module. Allow 5 modules for the entablature and 22 for the column. The columns should be spaced $9\frac{1}{2}$ modules from axis to axis. For detailed description of this order see Plate LI.

PLATE LI.

. ENTABLATURE, CAPITAL AND BASE OF THE GREEK CORINTHIAN ORDER.

- FIGURE 1. Section of Greek Corinthian Entablature and Capital.
 FIGURE 2. Elevation of Entablature and Capital.
 FIGURE 3. Plan of Capital.
 FIGURE 4. Plan of Dentils.

This plate represents the details of the Greek Corinthian intercolumniation. It will be observed that the module is always equal to one-half the diameter of the shaft of the column at its base. The module is divided into 18 parts and each part into 18 minutes. In the plate an astragal in the shape of a row of pearls has been added to the capital, although in the Monument of Lysicrates there is a hollow at this place. This added member should probably be of metal.

PLATE LII.

STUDY OF DOORWAYS.

This plate shows in Fig. 1 the entrance to the gardens of the Farnese Palace, on the Palatine in Rome, built in the rustic style by Vignola. The upper part, which has been suppressed in this plate, was not built by Vignola.

Figure 2 shows the entrance door of the Museum of the École des Beaux-Arts, Paris, of which M. Duban was the architect.

PLATE LIII.

STUDY OF DOORWAYS.

Figure 1 represents a doorway designed by Vignola for the Cancelleria Palace, Rome, but which was never executed. It will be noted that the width is equal to half the height.

The door-frame is about one-eighth of the width of the opening.

Figure 2 represents the doorway of the Palace of Caprarola, and is also by Vignola. The height is twice the width; the pilasters are eight diameters high, and the entablature is one-quarter the height of the pilasters.

PLATE LIV.

MAIN DOORWAY OF THE FARNESE PALACE, ROME.

- FIGURE 1. Elevation of the doorway.
FIGURE 2. Section.
FIGURE 3. Plan.
FIGURE 4. Detail of the cornice.

The main doorway of the Farnese Palace is given as an example of the round arched rusticated doorway. The projection of the cornice is occasioned by the stone balcony above it, but which is not shown in the plate.

PLATE LV.

STUDY OF DOORWAYS.

This plate shows the difference between an interior and exterior doorway of very similar form. Figure 1 shows a doorway in the second story of the Farnese Palace, built from the designs of Vignola.

Figure 2 shows the entrance door of the Church of St. Laurent in Damaso, after Vignola. On account of its richness this doorway harmonizes very well with the Corinthian order.

PLATE LVI.

DOORWAY OF THE PANTHEON AT ROME.

- FIGURE 1. Elevation of the Doorway.
FIGURE 2. Detail of the Cornice and of the Face of the Door-jamb or Architrave.
FIGURE 3. Section of the Door-jamb, or Architrave.

It has been established that the portico which precedes the rotunda of the Pantheon, and of which this doorway with its folding bronze doors is a part, was built in the time of Agrippa.

PLATE LVII.

STUDY OF WINDOWS.

In Figure 1 is represented the window of the lower story of the Palace of Caprarola. The height is double the width, and the frame, or architrave, is $\frac{3}{4}$ the width of the

opening. In Figure 2 is given an example of a window of the rustic order from the first story of the entrance building of the Villa of Pope Julius II. at Rome. The height is here also double the width.

PLATE LVIII.

DRAWING OF THE SHADOWS OF THE TUSCAN AND DORIC BASES.

- FIGURE 1. Vertical and Horizontal Projections of the Tuscan Base.
FIGURE 2. Vertical and Horizontal Projections of the Doric Base.

In order to find the shadows on the Tuscan and Doric bases cut the bases by vertical planes parallel to the direction of the ray of light; curves of section will thus be obtained, by the aid of which draw, point by point, the limits of the shadow and light, locating these points by tangents at 45°, which should be prolonged until they meet the curves of section.

In order to obtain these sections by means of the vertical planes at 45° it will be necessary, for the curved surfaces, to consider the intersection of these vertical planes at 45° with the sections of the same surfaces by horizontal planes. An examination of the plate, however, will make the method of drawing clear.

NOTE.—There are various methods in use for casting shadows on architectural drawings. That used for capitals and bases in the following plates is known as the "slicing method." It is desirable that the student should thoroughly understand and be familiar with this process, although in practice shorter and more practicable methods are used, which cannot be explained here.

The most satisfactory text-book on Shade and Shadows is that of Professor Pillet, translated by Prof. Julian Millard.

PLATE LIX.

DRAWING OF THE SHADOW OF THE TUSCAN CAPITAL.

To obtain the shadows on the capital the same process (the "slicing method") is employed as for the base, that is to say, by making use of the sections obtained by a series of vertical planes cutting the capital parallel with the ray of light. Besides the shadows on the capital there are also given the shadows cast by the capital upon a vertical plane passing through the axis.

PLATE LX.

SHADOW OF THE DORIC CAPITAL.

The same process is here used as for the Tuscan capital.

The capital surmounted by an architrave will cast a shadow such as that shown in this plate, upon a vertical plane parallel to the picture, and passing through the axis of the column.

PLATE LXI.

STUDY OF THE SHADOW OF THE CAPITAL OF THE IONIC ORDER.

Upon this plate are indicated the shadows of the Ionic capital seen from the front, and the shadows cast by the capital upon a vertical plane parallel to the picture plane and passing through the axis of the column. The method employed to obtain the different points of the shadow is always the same.

PLATE LXII.

STUDY OF THE SHADOW OF THE BASE AND OF THE CAPITAL OF THE IONIC ORDER SEEN IN PROFILE.

In the capital, as the edge of the cast shadow upon the shaft is made up of the expression of the listels of the volute and of the cincture, as well as of the line of shade on the cushion, it was necessary to draw separately the curves of the listel to obtain in plan the horizontal projections, and in the elevation the vertical projections of their principal points, and also the shade of the cushion as is indicated by the figures.*

For the base, it is necessary again to employ the method of vertical cuts, as A B, upon each of which the lines which are tangent to the base and parallel to the direction of the light give the limits of the shades upon the convex surfaces, while the secant lines give those of the cast shadows on the concave surfaces.

* The student will be able to follow this process if it is remembered that it is first necessary to determine the dividing line between light and shade upon the listels, cushion and cincture, shown in elevation in light and shade, and in the plan by hatching. To establish this line of division the profile of the listel is drawn, in dotted lines, at the right of the elevation, and that of the cincture of the cushion at the left. The remaining steps are obvious.

PLATE LXIII.

STUDY OF THE SHADOW OF THE CORINTHIAN CAPITAL.

FIGURE 1. Shadow of the Abacus and the Vase of the Corinthian Capital.

FIGURE 2. Shadow of the whole Corinthian Capital.

The shadow in Figure 1 is obtained by making a series of sections by means of vertical planes parallel to the direction of the light. In Figure 2 it is necessary to study separately the shadow of each of the ornaments of the capital in order to obtain an exact knowledge of the general shadow. Only the final result is here given.

PLATE LXIV.

DRAWING OF THE SHADOWS OF MODILLIONS, AND OF A PEDIMENT.

FIGURE 1. Study of the Cast Shadows of Pediment with Modillions.

FIGURE 2. Study of the Shadows of a Cornice of the Corinthian Order.

To determine the shadows cast by the cornice, draw from above the lines A C and B D, next the horizontal lines C E', D G', next by bringing down the points E, F, G, by means of lines at 45° the points E' F' G' will be obtained.

To draw the shadow of the pediment, first locate the lines M' P, O' N', R S, X Y, by making sections by means of vertical planes parallel to the ray of light, then locate successively the limits of the shadows, proceeding as with the cornice.

For Figure 2 the process is the same; it is only necessary to find a greater number of points to obtain the curves.

PLATE LXV.

SHADOWS OF THE TUSCAN PORTICO WITH PEDESTAL.

To find the cast shadows of this portico draw lines at 45° from all points in the plan which can cast shadows, to the planes upon which the shadows should be cast. From these points erect perpendiculars which may be intersected by lines at 45° from the corresponding points in the elevation. These intersections give the successive points of the desired shadows. For the details of the shadows cast by the capital directions are given on Plate 59.

PLATE LXVI.

STUDY OF THE SHADOWS OF THE IONIC ARCADE WITH PEDESTAL.

The shadows of this portico are determined by the same process as that employed in the preceding plates. The shadow of a niche is shown in order to explain the method by which it is drawn.*

The shadow of the niche falls upon two kinds of surfaces, — the cylindrical surface, and the spherical surface, forming the head of the niche.

To obtain that part of the shadow which falls upon the spherical surface of the niche draw through the centre O of the circle which forms the top of the niche a line at 45° to the horizontal, cutting the circle at the two points A and B. Erect a perpendicular to this line at O, cutting a line I H, which is made parallel to A B, in the point C, from which as a centre describe a semi-circle, of the same diameter as the niche. Then from the point D as centre and with the radius D E describe an arc cutting the line F D G, which is also parallel to A B, in the point F. At the point F erect a perpendicular to F D, cutting the line I H in the point I; then join I and D with a straight line which will be the diagonal of a cube, the side of which is equal to the radius of the niche, and at the same time will be the direction of

* The methods given at the foot of Plate LXVI being incorrect, a method is here given which has been adapted to the diagram shown in the plate.

the ray of light in the revolved plane. Through the point E draw a line parallel to the line I D until it intersects the semicircle at the point N, and join the points N and C by a straight line. This line will be the edge of the shadow on the spherical surface of the niche as it shows on the revolved plane. To obtain this line in elevation take several points, such as a, b, c, through which draw lines at 45° parallel to A B, and perpendicular to these lines, cutting the line I H in the points a' b' c'. From these points draw lines parallel to the ray of light I D cutting the line of shadow N C in the points a" b" c" which will be the representations in this revolved plane of the shadows cast by the points a b c on the sphere of the niche. To obtain these points in elevation draw through the points a" b" c" parallels to O C until they meet the lines at 45° passing through the points a, b, c, of the elevation. The intersections of these lines will give the points through which a curve can be drawn which will give the portion of the shadow on the spherical surface of the niche.

To obtain the shadow on the cylindrical surface of the niche take other points d, e, f, through which also draw lines at 45°, and project these points upon the line P Q of the plan in the points d' e' f'.* Through these projected points draw parallels to A' B' until they cut the circle representing in plan the depth of the niche. Through the points thus obtained draw perpendiculars which will cut the lines at 45° drawn from the corresponding points in elevation. These intersections give the last points of the second part of the curve of the shadow.

That part of the shadow which falls across the band of moldings within the niche is found by a method similar to the one employed in finding the shadow on the cylindrical surface, since the surfaces of these moldings, on which the shadow is visible, are also cylindrical.

* These letters have been omitted in the plate, but the points can easily be identified between P and A in the plan.

PLATE LXVII.

WOODEN FLOORS.

The name floor is given to the horizontal carpentry construction used to separate the different stories of a structure and to support the flooring of boards or parquetry. Floors are made up of three parts: first, the ceiling, second, the timber work, proper, and third the pavement or parquetry. When the floor is of small size joists only are used, spaced, as a rule, 33 c. m. on centres. When the floor is larger, the joists are carried by stronger timbers, called girders. Girders should be inserted at least 25 c. m. in the wall. The dimensions of timbers are proportioned to the load they are required to carry. To insure the proper preservation of wood it should be isolated, as far as possible, from the masonry, and closed in as little as possible.

Two examples of floor construction are here given with the principal arrangements commonly met with.

- A. Hearth of the fireplace.
- B. Header.
- C. Trimmer.
- D. Joist.
- E. Trimmers.
- H. Joist.
- M. Girder with joists on top.
- N. Girder with joists hung.
- P. Iron stirrup.

PLATE LXVIII.

EXTERIOR TIMBER FRAMING.

Timber work, though less strong, is used instead of masonry. Interior timber framing does not differ from that used for exteriors except that the former is thinner and lighter. For timber framing 4. metres in height the corner posts are made 25 c. m. section, the studs next openings 15 c. m., and studs and filling timbers from 10 to 12 c. m. When timber work is built three or four stories high the corner posts are made of from 25 to 30 c. m. section, and the sills and plates and girts from 20 to 25 c. m.

The spaces between the timbers are filled with boards or brickwork, if the timbers are intended to show, and by lath and plaster work if they are to be covered.

It is preferable to allow the construction to show.

- | | |
|--------------------|-------------------|
| a. Sill and Plate. | j. Filling in. |
| b. Corner Post. | m. Plate. |
| c. Window Studs. | n. Studs. |
| d. Brace. | p. Crossed braces |
| f. Trusses. | r. Joists. |
| g. Header. | s. Underpinning. |
| h. Sill-piece. | |

PLATE LXIX.

TRUSSES FOR STRAIGHT WOODEN ROOFS.

The name roof is given to the top part of a building upon which is applied the covering intended to protect it from the weather. To carry this covering it is necessary at intervals of from 4 to 5 m. to use trusses constructed of wood or iron. The disposition of these trusses varies according to the necessities of construction, the materials employed for the roof covering, and the climate. Three examples for straight roofs are here given.

FIGURE 1.

- | | |
|---------------|------------------|
| a. Tie beams. | f. Purlin. |
| b. King post. | g. Ridge Purlin. |
| c. Principal. | h. Jack rafter. |
| d. Strut. | i. Plate. |
| e. Strut. | l. Foot rafter. |

FIGURE 3.

- | | |
|---------------|------------------|
| a. Tie beam. | h. Strut. |
| b. Brace. | i. Purlin. |
| c. Tie beam. | k. Ridge Purlin. |
| d. King post. | l. Plate. |
| e. Principal. | m. Tie. |
| f. Brace. | n. Jack rafter. |
| g. Strut. | o. Foot rafter. |

PLATE LXX.

PRINCIPAL TYPES OF MANSARD ROOFS.

FIGURES 1, 2 and 3. Different Mansard Roofs with Lower Tie Beam.
FIGURE 4. Mansard Roof without Lower Tie Beam.

The trusses of a mansard roof are spaced as are those of other roofs, generally from 4 to 5 m. apart. When the types of roof shown in Figs. 1, 2, 3, are used for dwelling houses the braces f are left out and may be replaced by iron brackets or angles. The tie beam a then receives a series of timbers 0.33 on centres and 0.17 x 0.07, upon which are nailed the lathes for plastering.

- | | |
|------------------------|----------------------|
| a. Tie beam. | g. Struts. |
| b. Strut. | i. Angle plate. |
| c. Lower tie beam. | k. Ridge purlin. |
| d. King post. | l. Wall plate. |
| e. Principal of truss. | m. Foot rafter. |
| f. Braces. | n. Purlin and block. |

PLATE LXXI.

HIP ROOFS.

When roofs do not end in a gable a sloping framework is used instead. These triangular portions of roof placed at the end of a roof are called hips. If the walls are at right angles the hip is called *droite* (straight). If the walls are not at right angles the hip is called *biaise* (slanting).

- | | |
|----------------|-----------------------|
| A. Hip roof. | O. Hip rafter. |
| B. Pitch roof. | L. Jack rafters. |
| P. Truss. | R. Jack rafters. |
| Q. Half truss. | T. Tie beam of truss. |

PLATE LXXII.

JOINERY, STUDY OF DOORS AND WINDOWS.

- FIGURE 1. Elevation of Window from the Inside.
 FIGURE 2. Section on the line AB.
 FIGURE 3. Section on the line CD.
 FIGURE 4. Section on the line HG.
 FIGURE 5. Elevation of an Interior Door.
 FIGURE 6. Section on the line EF.
 FIGURE 7. Section on the line LM.

This plate shows, in general and in detail, interior doors and simple windows. Wood, being subject to expansion and contraction and warping, the problem to be solved by the joiner is to overcome these inconveniences. Rails and stiles should be made of sufficient strength to resist warping, and reinforced by pieces of iron such as the plates shown at g in Fig. 1. To avoid swelling and shrinking, pieces of small dimensions, and especially so across the grain, should be used. Woodwork should then be put together in such a way that the variations of the wood may take place without showing on the surface. The details of this plate will make clear the methods to be adopted for this purpose.

Exterior doors differ in no way from interior ones except in being made stronger.

- | | |
|-----------------------------|--------------------------|
| a. Jamb. | m. Jamb. |
| a'. Head and sill. | m'. Door-head. |
| b. Side rails. | n. Architrave. |
| b'. Meeting rails. | o. Stiles. |
| c. Upper rail. | o'. Stiles. |
| c'. Lower rail with drip. | q. Panels. |
| f. Muntins. | p. Panel mouldings. |
| g. Iron braces. | s. Lock. |
| h. Hinges. | r. Top and bottom bolts. |
| k. Double bolt with levers. | h. Hinge. |

PLATE LXXIII.

BARREL VAULTS AND CLOISTERED VAULTS.

- FIGURE 1. Barrel Vault.
 FIGURE 2. Cloistered Vault.
 FIGURE 3. Cloistered Vault with open top.

Figure 1 shows a straight barrel vault and the stone joints. Figures 2 and 3 show two cloistered vaults, that is,

vaults formed by the intersection of two barrel vaults. These two barrel vaults may be similar (of equal section) which simplifies the arrangement. When it is desired to admit light from above, the arrangement shown in Figure 3 is used.

PLATE LXXIV.

STUDY OF DIFFERENT GROINED VAULTS.

- FIGURE 1. Oblong Groined Vault.
 FIGURE 2. Vault with Double Groins and Pendentives.
 FIGURE 3. Vault with Double Groins and Cut-off Sides.

Groined vaults are formed by the intersection of one or more barrel vaults. More examples are given here in order to show some of the varieties of this kind of vault.

PLATE LXXV.

VAULTS UPON PENDENTIVES.

- FIGURE 1. Vaults upon Pendentives with Trumpets, Lunettes and Arches.
 FIGURE 2. Vault upon Pendentives with Lunettes.

The domical vault with pendentives is obtained by cutting a sphere by four vertical planes. When it is desired to allow the light to enter from above the sphere is cut by a fifth plane, this time horizontally.

Two types of the construction of this kind of vault are given. Reference should be made to special treatises upon stereotomy for further details.

PLATE LXXVI.

STUDY OF CAISSONS.

- FIGURES 1 AND 4.—Section upon a plane parallel to the elements of the Barrel Vault.
 FIGURES 2 AND 5.—Section upon a plane perpendicular to the elements of the Barrel Vault.
 FIGURES 3 AND 6.—Development of a portion of the Vault.
 FIGURE 7.—Section of a Dome with Caissons.
 FIGURE 8.—Plan of a quarter of the Dome and Caissons.
 FIGURE 9.—Development of a segment for the purpose of drawing the Caissons.

Caissons are hollow compartments formed upon the surface of a vault in order to diminish the weight, and at the same time retain the desired strength. Caissons give an opportunity for enrichment, either by their form or by applied ornament, appropriate to the building in which they are employed. Several examples are given here.


To draw in projection the caissons of a barrel vault first develop a portion of the vault sufficient to show all the details of the decoration, then project all the parts by means of elements of the surface.

The surface of a domical vault cannot be exactly developed. It is necessary, therefore, to work by approximation, by developing a segment, which should be taken as small as possible.

GLOSSARY

Abaque. Abacus.	Chevêtres. Trimmers.	of the guttæ, or drops, in the architrave under the triglyphe.
Aisselier. Brace.	Chevron. Jack rafter.	Détail d'une goutte du soffite. Detail of a drop of the soffit.
Annelet. Annulet, or cincture.	Chevrons. Jack rafters.	Dez. Die.
Annelet, orle ou cincture. Annulet, or cincture, or fillet.	Cincture. Cincture.	Diamètre de la colonne. Diameter of the column.
Antes. Antæ.	Clef. Key, or key-stone.	Dorique. Doric.
Appui. Sill-piece.	Colonne. Column.	Doucine. Cyma recta.
Arbalétrier. Principal.	Comble. Roof.	Écharpe. Brace.
Arcade. An opening arranged in masonry, and composed of an arch supported either on columns or on piers.	Comble droit. Straight roof.	Elevation. Elevation.
Architrave. Architrave.	Composite. Composite.	Elevation principale. Principal elevation.
Archivolte. Archivolt.	Congé. Congé, or apophyge.	Empanons. Jack rafters.
Arctier. Hip rafter.	Congé inférieure. Lower congé.	Entablement. Entablature.
Assises. Courses, of stonework.	Contrefiche. Strut.	Entraît. Lower tie beam.
Atre de la cheminée. Hearth of the fireplace.	Coque des oves. Shell of the eggs.	Entr'axe. Distance between one axis and another.
Axe. Axis.	Corinthien. Corinthian.	Entrecolonnement. Intercolumniation.
Axe du chapiteau. Axis of the capital.	Corniche. Cornice.	Équerre en fer. Iron brace.
Baguette. Baguette, or astragal.	Corniche de la porte. Cornice of the doorway.	Étrier en fer. Iron stirrup.
Balustrade. Balustrade.	Corniche du piédestal. Cornice of the pedestal.	Eschelle. Scale.
Base. Base.	Côte. Side, meaning in this case side elevation.	Eschelle de la plan et de la coupe. Scale of the plan and of the section.
Base de la colonne. Base of the column.	Côte de la cannelure. Side of the flute, referring to the listel between the flutes.	Eschelle des, etc. Scale for, etc.
Bâti de dormant. Jamb, of door or window.	Coupe. Section.	Eschelle du detail. Scale for the detail.
Baton. Astragal, or narrow band.	Coupe larmes. Drip, or drip moulding.	Étage. Story (of a building).
Baton ou baguette. Astragal.	Coupole. Dome.	Face. Fascia.
Battants de noix contre dormant. Side rails.	Coussinet. Cushion.	Face de l'abaque. Fascia of the abacus.
Battants meneaux. Meeting rails.	Coyau. Foot rafter.	Face de l'architrave. Fascia of the architrave.
Blochet. Tie.	Crémone. Double bolt, with levers.	Face de l'archivolte. Fascia of the archivolt.
Cadres de panneaux. Panel mouldings.	Croix de St. André. Cross bracing in the form of the letter X.	Face de l'imposte. Fascia of the impost.
Caissons. Caissons.	Croupe. Hip roof.	Face du tailloir. Fascia of the abacus.
Canaux. Channels. The channels of the triglyph.	Croupe biaise. A hip roof upon a building with walls not at right angles.	Faitage. Ridge purlin.
Cannelure. Flute.	Croupe droite. A hip roof upon a building with walls at right angles.	Faux chevêtres. Joists.
Cannelure demi-circulaire. Semi-circular flute.	Cymaise. Cymatium.	Fenêtres. Windows.
Cathète. Cathetus.	Dards. Darts.	Ferme. A roof-truss.
Caulicole. Cauliculus.	D'axe en axe. From axis to axis.	Feuille. Leaf.
Cavet. Cavetto.	Dé ou dez. Die.	Feuille des caulicoles. Leaf of the cauliculi.
Chambranle. Door-jamb, or architrave. Window-jamb, or architrave.	Dé ou tronc. Die.	Filet. Fillet.
Chapiteau. Capital.	Décharges. Trusses.	Filet ou anneau. Fillet, or ring.
Chapiteau des triglyphes. Capital of the triglyphs.	Demi ferme. Half truss.	Fleuron. Rose, or flower.
Cheminée. Fireplace.	Denticules. Dentils.	Frise. Frieze.
	Détail de la corniche. Detail of the cornice.	
	Détails des gouttes dans l'architrave sous le triglyphe. Details	

Frise de la porte. Frieze of the doorway.	Montants. Stiles.	Rez-de-chaussée. First story, ground floor.
Fronton. Pediment.	Moulures. Mouldings.	Rosace. Rose, or flower.
Fût ou vif de la colonne. Shaft of the column.	Moulures de chambranle. Mouldings of the architrave (of the door or window).	Rose. Rose.
Galbe. Entasis. The swelling of the shaft of a column.	Mutule. Mutule.	Rose, ou fleuron. Rose, or flower.
Génératrices. Generatrices.	Mutule avec gouttes en dessous. Mutule with drops beneath.	Sablière. Plate.
Gorgerin. Neck, or necking.	Nu de l'architrave. Surface, or plane, of the architrave.	Sablières. Plates.
Gorgerin ou frise. Neck, or necking, of the shaft.	Nu du fût. Face of the shaft.	Sablières de chambrée. Plate.
Gousses. Pods.	Nu du vase. Face of the vase.	Salle. Hall.
Goutte. Drop.	Œil de la volute. Eye of the volute.	Scotie. Scotia.
Goutte carrée. Square drop.	Ombre. Shadow.	Scotie inférieure. Lower scotia.
Goutte droite. Straight drop.	Ombre portée. Cast shadow, as distinguished from shade.	Scotie supérieure. Upper scotia.
Goutte rampante. Sloping drop.	Ombre propre. Shade, as distinguished from cast shadow.	Serrure. Lock.
Goutte ronde. Round drop.	Ove. Ovolo.	Socle. Socle.
Gouttes. Drops, or guttæ.	Oves. Eggs.	Socle de la base. Socle of the base.
Gouttière. Gutter.	Pan de bois. Framed timber work.	Socle maçonnerie. Base of masonry, underpinning.
Grande feuille. Large leaf.	Panne de lierne. Purlin.	Socle ou base du piédestal. Base of the pedestal.
Grande salle. Large hall. In this case, applied to the cella of the Roman temple.	Panneaux. Panels.	Soffite. Soffit.
Guettes. Braces.	Pannes. Purlins.	Solive. Joist.
Hauteur de, or hauteur du, etc. Height of, etc.	Parties. Parts, the divisions of a module.	Solives. Joists.
Hauteur de l'arcade. Height of the arcade.	Paumelle. Hinge.	Solives d'enchevêtrement. Headers.
Hauteur de la colonne. Height of the column.	Pendentif. Penditive.	Tailloir. Abacus.
Imposte. Impost.	Petite feuille. Small leaf.	Talon. Cyma reversa.
Ionique. Ionic.	Petits bois. Muntins.	Talon renversé. Reversed cyma-reversa.
Jamb de force. Brace.	Piédestal. Pedestal.	Tirant. Tie-beam.
Jambette. Strut.	Plan. Used either for plan, as in architecture, or plane, as in geometry.	Tore. Torus.
Jet d'eau. Drip.	Plancher. Floor.	Torse. Twisted.
Lambourde. Summer attached to girder.	Plinthe. Plinth.	Toscan. Tuscan.
Largeur de, or largeur du, etc. Width of, etc.	Plinthe ou socle de la base. Plinth of the base.	Tournisse. Stud.
Largeur de l'arcade. Width of the arcade.	Poinçon. King post.	Tracé. Drawing, or representation.
Larmier. Corona.	Porte. Doorway.	Traverse de dormant. The head, and the sill of a door.
Ligne. Line.	Portique. Portico.	Traverse du haut. Upper rail.
Ligne droite. Straight line.	Poteau. Post.	Traverses. Stiles.
Ligne spirale. Spiral line.	Poteaux. Posts.	Triglyphe. Triglyph.
Lincoir. Trimmer.	Poteaux corniers. Corner posts.	Triglyphes avec canaux. Triglyphs with channels.
Linteau. Lintel.	Poteaux d' huisserie. Window studs.	Tronc. Shaft.
Listeau. Listels. Plural of listel.	Poutre. Girder.	Tympan. Tympanum.
Listel de l'abaque. Listel of the abacus.	Poutre avec lambourde. Girder with joists hung.	Tympan du fronton. Tympanum of the pediment.
Listel, ou cincture. Listel, or cincture.	Poutre portant solives. Girder carrying floor joists.	Vase. Vase.
Longs pans. Slope of the roof.	Projection horizontale. Horizontal projection.	Verrou. Bolt.
Marches. Steps.	Projection verticale. Vertical projection.	Volute. Volute.
Menuiserie. Joinery.	Quart de rond. Quarter round.	Voûte. Vault.
Métope. Metope.	Quart de rond, ou ove. Quarter round, or ovolo.	Voûte d'arête. Groined vault.
Mètres. Metres. Equal to 39.37 inches.	Reglet. Reglet, or listel.	Voûte d'arête barlongue. Oblong groined vault.
Modillons. Modillions.	Reglet, ou listel. Reglet, or listel.	Voûte en arc de cloître. Cloistered vault.
Module. Module. An arbitrary unit of measure.	Remplissage. Filling in.	Voûte en arc de cloître ouverte par le haut. Cloistered vault open at the top.
	Renflé. Having entasis.	Voûte en berceau. Barrel vault.
		Voûte sur pendentifs. Vault upon pendentives.



P. Esquisse del.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Ecoles, Paris.


Strassmann Sc.

Un ordre est l'ensemble architectural formé par les éléments nécessaires pour soutenir des parties pleines au dessus de parties vides. Quand il est simple, l'ordre comporte un entablement, une Colonne et un piédestal. Le piédestal n'est pas indispensable.


Les proportions relatives de ces éléments devant varier suivant la nature des matériaux mis en œuvre, et le degré de richesse que l'on désire obtenir, on a ramené les divers systèmes à cinq types que l'on nomme : le Toscan, le Dorique, l'Ionique, le Corinthien et le Composite. Les proportions que nous donnons d'après Vignole n'ont rien d'absolu, mais on ne devra pas perdre de vue que ce sont des moyennes et qu'en son courtant trop et sans raison on s'expose à commettre de véritables contre-sens.

Cette planche offre le parallèle des cinq ordres d'architecture donnés par Vignole, nous faisons voir par la ligne de division de hauteur en 3 parties (cette partie étant considérée comme le module) la proportion que les ordres ont entre eux : le Toscan le Dorique et l'Ionique ont les mêmes proportions relatives, comme on le voit par les lignes AA, BB, CC, c'est à dire que pour une même hauteur de la colonne et l'entablement le 1/3 de la hauteur de la colonne, il n'y a que pour les ordres Corinthien et Composite que l'entablement est plus élevé, et que, plus que le piédestal en haut d'un 1/3 de hauteur comme il conviendrait en suivant la même proportion que celle indiquée pour les trois premiers ordres, à 1/3 de module de plus ou 7 modules en tout. Le module se divise en 12 parties pour les deux premiers ordres, et en 18 parties pour les trois derniers.

Cavet




Quart de rond




Le tracé des droites et des circonférences tangentes est indispensable pour opérer ce que l'on appelle Raccordement. Cette opération consiste à lier les lignes les unes aux autres de manière à ne former entre elles aucun Jarret. Les raccords s'emploient en architecture dans une foule de cas, et notamment dans le tracé des moulures. Les moulures se divisent en simples et composées. Les principales moulures sont: le Cavet, le Quart de rond et la Tore. Les moulures composées: la Doucine, le Talon et la Scotie. Le cavet est un quart de cercle rentrant, dont la saillie égale la hauteur. L'inspection des 3 premières figures suffira pour en comprendre le tracé.

Tore




Doucine




La Doucine ou Gueule droite est une moulure sinuose dont la partie supérieure est concave et la saillie égale à la hauteur. Voici son tracé: la saillie AC étant prise égale à la hauteur AB on joint BC par une droite qu'on divise en deux parties égales au point D. Sur les côtés DB, DC on construit l'un en dedans, l'autre en dehors, deux triangles équilatéraux qui déterminent les centres O O' des arcs de cercle CDB qui forment la doucine.

Talon



Scotie



Le Talon est une moulure formée par deux arcs de cercle raccordés dont l'inspection de la figure explique le tracé.

La Scotie est une moulure creuse placée ordinairement entre deux portées verticales, tracé: les parallèles m et XT et leurs points respectifs T et étant donnés par les points de tangence T et par n quelconque pris sur m et élevé les perpendiculaires tO' , Ti , nX . Prenez $Xy = \frac{1}{2} Xn$ et par y menez yi parallèle à m qui déterminera le point par son intersection avec Ti décrivant du point i le quart de cercle $T'K$, portez $iO = \frac{1}{2}$ de Ki , du point O décrivez la $KH = \frac{1}{2}$ arc TK portez ensuite $OZ = \frac{1}{2}$ de OH portez $HZ = tQ$ joignez Z et Q par une droite ZQ et élevez une perpendiculaire MO au milieu de cette droite qui déterminera O' , le point Z sera le centre de HL et O' de t .

T. Regnié del.


CHARLES SCHMID ÉDITEUR, 51 Rue des Écoles, Paris.

Stralsmarin 80

La distance d'une colonne à l'autre s'appelle l'entrecolonnement. L'entrecolonnement ne doit jamais être assez grand pour que la solidité réelle ou apparente ait à en souffrir; on s'est donc pour empêcher l'accès de la lumière ou le passage des hommes dans une colonnade, les entrecolonnements doivent être égaux à moins qu'il n'y ait nécessité d'ouvrir un grand passage au milieu pour une entrée principale.

PL. V.






P. Esquié del.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Écoles - Paris.

Strasmann Sc.

L'ordre Toscan est simple et rustique, son caractère principal est la force et ne supporte aucun ornement d'azur, à l'exception des bossages ou autres décorations rustiques. Bien qu'il ne soit pas dans l'usage de faire un piédestal à l'ordre Toscan, Vignolo a cru devoir l'indiquer pour suivre l'ordre qu'il s'était proposé pour son traité des cinq ordres, il donne au piédestal le tiers de la hauteur de la colonne ce qui donne 4 modules 8 parties pour sa hauteur, y compris la base et la corniche qui ont chacun 1/2 module de hauteur, le dé ou tronc a 3 modules 7/8 de hauteur et sa largeur est la même que celle du socle de la base qui est de 4 modules 9 parties, la hauteur de la base de la colonne est de 4 modules qui divisée en deux parties égales, donne l'une le socle et l'autre le torse avec la ceinture donc la hauteur est de 2 parties; Dans cet ordre la ceinture ou listel C n'est pas comprise dans la hauteur du fût, on fera observer que le module est déterminé par le diamètre de la colonne qui est toujours de 4 modules, il est divisé en 12 parties ou minutes pour l'ordre Toscan.



P. Esquis del.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Écoles - Paris.

Strosmann, Sc

L'entablement toscan a la $\frac{1}{2}$ de la hauteur de la colonne ce qui lui donne par conséquent 3 modules $\frac{1}{2}$ dont 1 module pour l'architrave, 1 module 2 parties pour la frise et le reste pour la corniche, on voit dans la coupe de cette corniche l'indication du refoulement du larmier contre l'écoulement des eaux et par ce moyen les empêcher de couler sur les autres parties de l'entablement, le chapiteau a de hauteur 1 module la diminution du fût de la colonne est de cinq parties sous l'abaque, ou 2 parties $\frac{1}{2}$ de chaque côté. — Au dessous se trouve indiqué le plan du chapiteau et de l'entablement toscan, cette indication servant à bien faire comprendre le retour d'angle de la corniche.

La figure 5^{me} qui donne l'imposte et l'archivolte de l'arcade toscane avec piédestal n'a point été faite avec les mesures données par Vignole, on a pensé devoir les corriger en quelques parties pour leur donner plus de grâce.




Fig. 1. Élévation des frontons droits et circulaires.
 Fig. 2. Élévation latérale des frontons.
 Fig. 3. Coupe.
 Fig. 4. Tracé des frontons droits.
 Fig. 5. Tracé des frontons courbes.

CHARLES SCHMID, ÉDITEUR, 31, Rue des Écoles, Paris.

Un fronton n'est autre chose qu'un pignon, orné ou masqué il n'est donc bien placé que là où le pignon existe, la proportion des frontons est assez difficile à établir car elle varie dans les différents ordres. Nous donnons ici le modèle indiqué par Serlio qui nous paraît très convenable pour les ordres Toscan et Dorique. L'inspection des figures suffira pour comprendre les détails.

Proportion soignée

P. Esquié, del.


CHARLES SCHMID, ÉDITEUR, 51, Rue des Ecoles — Paris.

Strasman, So.

Pour dessiner un entrecolonnement dorique il faut diviser la hauteur totale en vingt parties, une pour l'entablement et les quatre autres pour la colonne, ou bien comme le dit Vignole, diviser la hauteur en 20 parties, dont l'une sera le module. Ce module se divise comme pour le Trosien en 22 parties. La colonne aura 16 modules ou 8 fois le plus grand diamètre. On donnera 3 modules pour la base, 1 mod. pour le chapiteau, et il restera 11 modules pour la hauteur du fût. L'entablement a 4 mod. dont 2 mod. pour l'architrave, 1 mod. 1/2 pour la frise, et 1 module 1/2 pour la corniche. Toutes ces parties réunies donneront 20 modules pour la hauteur générale de l'ordre.

Dans la frise les triglyphes sont toujours à plomb sur l'axe des colonnes. Ils ont 4 module de largeur. Les métopes sont carrées; elles ont 1 module $\frac{1}{2}$. On peut les orner de divers ornements tels que têtes de bœuf, armoiries, palères &c. L'entrecolonnement dorique est toujours déterminé par le nombre des triglyphes. La colonne a 50 cordons. Le galbe du fût se trace comme pour le taurin.


PORTIQUE DORIEN AVEC PIÉDESTAL



CHARLES SCHEID, ÉDITEUR, 57, Rue des Écoles - Paris.

J. Esprit, del.

Dezmann, sc.



P. Esquié, del.

CHARLES SCUDÉ, ÉDITEUR, 31, Rue des Écoles - Paris.

J. Neumann, sc.

Comme pour l'ordre Toscan, le module se divise en 12 parties ou minutes, le piédestal a de même 5 modules & parties qui est le $\frac{5}{12}$ de la hauteur de la colonne, la base de la colonne a un module, une baguette de 1 partie se prive sur la hauteur du tore ce qui rend cette base plus élégante et plus légère que celle de l'ordre Toscan, on peut faire les colonnes Doriques avec ou sans cannelures, pour obtenir les cannelures on divise la circonférence de la colonne en vingt parties égales qui vont de base à autant de triangles équilatéraux dont le sommet a. est le centre d'une portion de cercle b.c. comme on le voit dans la figure F. si on veut faire les cannelures plus prononcées il faut (Fig. E.) joindre les points b.c. par une droite, élever la perpendiculaire a.d. tracer le demi cercle b.d.o. et le point d. sera le centre d'une autre portion de cercles qui donne des cannelures plus profondes.

La coupe du piédestal indique le refoulement fait sous le larmier et que l'on appelle coupe larmes parcequ'il a pour objet d'arrêter les eaux pluviales, qui sans ce moyen, pourraient dégrader promptement les autres parties de ce piédestal.

Fig. 1




Fig. 2




Fig. 3




Fig. 1 Section d'un temple

Fig. 2 Plan de la partie

Fig. 3 Coupe sur l'axe de la


porte

A Assises
B Corniche de la porte
C Base de la porte
D Chambraille
E Plinthe

6 1 2 3 4 5 6 7 modules

CHARLES SCHMID, ÉDITEUR, 57 Rue des Écoles, Paris
Celle planche représente un portique Dorique Matabais de trois entablementements. L'entablement est déterminé par le nombre des triglyphes. Le maximum ne doit pas dépasser trois entab. - triglyphes. — Pour le tracé du fronton, on se reportera à la planche suivante.

Strasbourg, 57



P. Kœnig del.


CHARLES SCHMID, ÉDITEUR, 31, Rue des Écoles, Paris.

Strasbourg, etc.

L'entrecolonnement Ionique se fait de même que les entrecolonnements toscans et doriques, en divisant la hauteur totale de l'ordre en 5 parties dont les 4 inférieures forment la hauteur de la colonne; on divise cette hauteur en 18 parties ce qui donnera le module, le module de cet ordre se divise en dix-huit parties ou minutes pour les diverses moulures qui composent cet ordre, on a besoin de cette division du module en 18 parties à cause des moulures qui sont plus nombreuses dans cet ordre qui est beaucoup plus délicat que les deux ordres précédents, il s'emploie ordinairement dans les intérieurs à cause de son élégance ou extérieurement dans les seconds étages des édifices; les anciens l'ont employé dans divers temples un bel exemple de cet ordre se voit à Rome au temple de la Fortune virile, on remarquera que le chapeau d'angle A se trouve sur ces colonnes à l'entablement, l'on aperçoit toujours les volutes.

PORTIQUE IONIQUE AVEC PIÉDESTAL

20



Le portique ionique avec piédestal s'emploie principalement dans les grands édifices surtout pour le premier étage. Sa disposition est plus élégante dans les formes que celle des deux autres précédents, dont le caractère particulier annonce plus la force et la solidité.


Pour tracer le portique ionique avec piédestal, il faut diviser la hauteur totale en 13 parties et demi ou modules.

Le piédestal, y compris la base et la corniche avec 6 modules de hauteur soit le tiers de la colonne entière. Il restera par conséquent 8 modules et $\frac{1}{2}$ pour la hauteur de l'entablement selon la règle adoptée par Pignolo, la largeur des piédestals est de 8 modules et l'arcade et toujours en hauteur le double de la largeur.


La coupe, faite sur l'axe d'une arcade montre une voûte en berceau avec doubleaux au droit des colonnes et la pénétration.



1 2 3 4 5 6 7 8 9



Longueur de l'arcade 11 mod.
Largeur d'axe en axe 5 mod.






CHARLES SCHMID, ÉDITEUR, 51, Rue des Ecoles, Paris

L'ordre Ionique occupe par sa forme et sa décoration le milieu entre le Dorique qui représente la force et la solidité, et le Corinthien qui est le type parfait de l'élégance et de la richesse. Le goût si égaré des grecs avait besoin d'un intermédiaire entre deux systèmes, l'un d'ordonnance simple, grave, et l'autre plus orné, plus riche, plus noble et plus agréable à l'œil. L'ordre Ionique fut le résultat de ce besoin, et de la nécessité de concilier ces deux principes, et de les réunir dans un seul et même système.

de la richesse. Le goût s'oppose aux gressins, mais il aime la robe d'ivoire. Le piedestal l'omique que nous donnons dans cette planche a la tiers de la hauteur de la colonne, c'est-à-dire 6 modules, sans empatement et sa base est sur un socle. La module de hauteur, le dix a 5 modules de hauteur, les deux filets compris, la base que nous donnons est celle de l'igoule, nous donnons plus loin l'exemple de la base antique que les anciens employaient, celle a un module de hauteur, sans y comprendre le listel ou ceinture, le fût de la colonne est orné de 25 cannelures demi-circulaires qui se terminent couramment à la naissance du corinthe, la largeur de la cote de la colonne a les 7/8 de l'ouverture de cette cannelure.

ENTABLEMENT ET CHAPITEAU DE L'ORDRE IONIQUE AVEC COUSSINETS

22





CHARLES SCHMID, ARCHITECTE, 31, rue des Ecoles, Paris.

BRUSMANS, etc.

P. Esquie del.

Cette planche représente en grand les détails de l'entablement et du chapiteau de l'ordre ionique ainsi que les impostes de cet ordre. Le chapiteau donné est celui d'une colonne d'angle établie d'après les principes du temple de la Fortune nile à Rome. Grâce à cette disposition spéciale le chapiteau parait bien équilibré lorsque l'un est sur la diagonale. Les chapiteaux des colonnes à la suite sont composés de deux parties semblables au côté A de la fig. 1.




P. Esquis, del.

CHARLES SCHMID, EDITEUR, 51, Rue des Ecoles, Paris.

Strasman, Sc.

Nous donnons comme complément de l'ordre Ionique un acrople d'un temple bâti par les Romains, qui le dédièrent à la fortune virile. C'est le plus bel exemple de cet ordre qui nous soit resté aussi complet. Nous avons cru devoir le placer sous les yeux des élèves qui commencent, afin de les engager dès leur début dans l'art de l'architecture, à ne jamais s'écarter des bonnes traditions, et à se bien pénétrer des beautés de l'antiquité.



P. Esquié del.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Ecoles - Paris.

Strasman, Sc.

P. Esquisse del.

Pour tracer l'entrecolonnement corinthien on divise la hauteur totale en 23 parties, dont une sera le module, qui se divise aussi en 18 parties ou minutes comme dans l'ordre ionique. Signale fixe la largeur entre les colonnes à 4 modules $\frac{1}{2}$, afin d'accorder la division des modillons dans la corniche, et qu'il s'en trouve toujours un sur l'axe de chaque colonne.

On s'en servira sur tous les autres, on l'emploiera principalement pour les grands monuments, tels que les temples et les

Cet ordre l'emporte par sa magnificence sur tous les autres, on l'emploiera principalement pour les grands monuments, tels que les temples et les palais.






Fig. 3

Fig. 4




Fig. 2

Fig. 1

Fig. 6

Fig. 1 Filation de l'intubement
et du rhinopneux cornu
Fig. 2 Corps de l'intubement
et du rhinopneux cornu
Fig. 3 Corps de la corne
Fig. 4 Plan de la corne
Fig. 5 Imposte et archivolte de
l'arcade sans piedestal
Fig. 6 Imposte et archivolte de
l'arcade avec piedestal

La hauteur de l'entablement se divise en 10 parties dont 3 pour l'architrave, 3 pour la frise et 4 pour les corniches. Au dessus de chaque médillon on place un objet de décoration en une tête de lion. C'est pour ces motifs que dans l'entablure il est dit que les corniches plantées. A notre époque ils ne pourraient servir que pour les trop plaines.

q. 1 et 3 parties 10

+ 0

1


11

1772

11


Dans un fronton la partie triangulaire comprise entre les bras corinthes s'appelle Tympan. C'est dans cet espace que les arabes plaçaient des figures ainsi qu'on a pu le constater pour plusieurs temples. Les temples corinthiens à cause de la richesse de l'ordre comportaient presque toujours en guise de décoration. On plaçait quelquefois aussi au-dessus de ces frontons dans les angles et au sommet, des figures ou autres motifs formant attouche.

Section suivant AB



Profil du Modillon


Face du Modillon



P. Exquis del.

CHARLES SCHMID, EDITEUR, 35 Boulevard des Capucines, Paris.

Desmarest, sc.




Plan

Elevation

Coupe

P. Esquisse. del.
 Cette planche donne un exemple de temple d'ordre corinthien à six colonnes. On remarquera que l'échelle de cet ensemble architectural est en mètres et non en modules afin d'indiquer les proportions réelles.
 Specimen, ex
 CHARLES SCHMID, EDITEUR, 51, Rue des Ecoles, Paris.



P. Esquiè del.


CHARLES SCHMID, EDITEUR, 57, Rue des Ecoles, Paris.

Pour dessiner l'entrecolonnement composite on emploiera le même moyen que celui dont on s'est déjà servi pour l'ordre corinthien, on aura soin toutefois de remplir les colonnes d'une demi-partie de module au tiers de la hauteur du fût et de les diminuer progressivement jusqu' sous l'astragale.


PORTIQUE COMPOSITE SANS PIEDESTAL

Ce portique sera employé dans les mêmes occasions que celui de l'ordre corinthien. Il se compose de même en décrivant la hauteur totale en cinq parties, celle du haut pour l'entablement et les quatre autres pour les colonnes; l'entablature aura juste en hauteur le double de sa largeur.

Dans la coupe, nous supprimons la salle
voûtée en berceau, ce dernier éton-
nabi de manière à éviter les pénétrations des
arabes.



PORTIQUE COMPOSITE AVEC PIÉDESTAL




Ce portique peut être employé pour les façades des palais, ainsi que dans les galeries, et les grandes salles pour tout où l'on voudra décorer architecturalement une grande pièce.

Pour les explications voir la planche relative à l'ordre corinthien avec piédestal.

La coupe représente une voûte en cul-de-poule sur pendentifs.

parties basses 1 2 3 4 5 6 7 modules




Longueur de l'arcade 12 mod.
d'axe en axe

CHARLES SCHIND, EDITEUR 61, Rue des Ecoles, Paris

P. Enghelmann del.

Sturm und Drang

Fig. 3. Profil du piédestal
et de la base compositeFig. 1. Elevation du piédestal
et de la base de l'ordre composite.Fig. 2. Coupe du piédestal
et de la base composite


P. Roqué, del.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Écoles - Paris.


Struassmann, Sc.

Les proportions du piédestal et de la base de l'ordre composite sont les mêmes que celles de l'ordre corinthien, la différence n'existe que pour les moulures de la cymaise ou de l'empattement. Vignole n'a pas orné les moulures de ce piédestal, mais il ne faut pas regarder cela comme une règle absolue ou que cet ordre participe de l'ionique et du corinthien. Le fût de la colonne comporte comme le corinthien 24 cannelures, les côtes entre les cannelures ont les $\frac{2}{3}$ de la largeur de la cannelure.






Coupe



Elevation principale

Plan



Côté

P. Enquist, del.

L'Arc de Titus dont nous donnons ici la restauration peut servir à juger de la manière dont les Arcs romains employaient l'ordre composite. On peut employer cet ordre pour les monuments qui exigent une très grande élévation.

CHARLES SCHMID, EDITEUR, 14, Rue des Écoles, Paris.

Deutscher, sc.




Fig. 1

Fig. 2


Fig. 1 Elevation des
deux ordres superposés
Fig. 2 Coupe des deux
ordres superposés
Fig. 3 Plan des deux
ordres superposés
Fig. 4 Plan d'une pile
du vestibule

CHARLES SCHMID, ÉDITEUR, 51, Rue des Écoles - Paris.

Struemann, Sc.

P. Esquié, del.

Nous donnons ici un premier exemple de superposition de l'ordre ionique à l'ordre dorique d'après le théâtre de Marcellus à Rome. On remarquera que la colonne ionique est plus courte que la colonne dorique de la hauteur d'un module de l'ordre dorique ou demi diamètre.



Lorsque l'on juxtapose deux ordres, on donne généralement au plus petit les $\frac{2}{3}$ de la hauteur du plus grand. Il est bon, de ne pas trop s'écarter de ce rapport lorsque l'on ne peut le suivre exactement.
Comme exemple nous donnons le portique dit d'Octavie à Rome, pour lequel ce principe a été observé.






Fig. 1 Elevation du portique d'Octavie
Fig. 2 Plan du portique d'Octavie
Fig. 3 Détail du portique




PARALLÈLE DE BALUSTRADES


Balustrade toscane




Balustrade ionique



Balustrade dorique



Balustrade corinthienne




CHARLES SCHIND, ÉDITEUR, 51 Rue des Écoles - Paris.

Sturmman, Sc.

P. Esquié, del.

La balustrade n'est autre chose qu'un appui ou revêtement. Sa hauteur est tantôt un peu plus ou tantôt un peu moins de un mètre. Elle doit être élevée sur un socle suffisant pour éléger en perspective sa base de la saillie de la corniche. Les piliers d'arrêt seront toujours en rapport comme richesse avec l'ordre avec lequel les balustrades doivent servir. Il ne faut pas confondre une balustrade avec un attique. Une balustrade étant toujours en rapport avec l'échelle humaine tandis que l'attique est proportionné au monument. — Nous donnons ici les quatre principaux types de balustrades pour servir de mesure.



P. Esquié, del.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Ecoles - Paris

Serasmann, Sc.

Les divers temples Grecs dont les restes sont parvenus jusqu'à nous étaient tous de proportions très différentes. Nous donnons ici un tracé de l'ordre dorique qui se rapproche très sensiblement du Parthénon à Athènes. Pour trouver le module de cet ordre, étant donné la hauteur à atteindre, on divisera en 14 parties $\frac{1}{2}$, une de ces divisions sera le module. On prendra 11 modules pour la colonne et 3 modules $\frac{1}{2}$ pour l'entablement. Pour le tracé du détail on se reportera à la planche 47.

On remarquera que comme pour les autres ordres doriques que nous avons donné au début, nous avons divisé le module en 14 parties et pour pouvoir donner les mesures des éléments plus fins, subdivisé chacune de ces parties en 12 minutes.

Fig. 1 Élévation de l'entablement et du chapiteau de l'ordre Dorique Grec.


Fig. 2 Coupe de l'entablement et du chapiteau de l'ordre Dorique Grec.

Fig. 3 Coupe de la corniche de l'entablement de l'ordre Dorique Grec, face latérale.

Fig. 4 Élévation latérale de la corniche de l'entablement de l'ordre Dorique Grec.

Fig. 5 Section du triglyphe.

Fig. 6 Section du fût de la colonne à sa partie inférieure.




CHARLES SCHMID, ÉDITEUR, 51, Rue des Écoles - Paris.

Strassmann, Sc.

P. Besquié, del.

Nous donnons ci-dessous le tracé d'un entablement et d'un chapiteau d'ordre Dorique dont les proportions se rapprochent très sensiblement du Parthénon à Athènes. On remarquera que la colonne donnée n'est pas symétrique et est de 2 mod. et 6 à la base. Les autres colonnes doivent avoir exactement 2 diamètres. Cette différence provient de ce que l'on donnait une inclinaison à la colonne vers l'intérieur pour augmenter la stabilité. On remarquera que le triglyphe dans les ordres Grecs est exactement à l'angle de la frise et non sur l'axe de la colonne comme dans les Doriques Romains ou de la Renaissance. Cette disposition est beaucoup plus logique, les triglyphes étant des points supportant la corniche et les métopes de simples remplissages.




P. Boqué, del.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Boîtes - Paris.

Straßmann, Sc.

Pour dessiner l'entrecolonnement Ionique Grec on divisera la hauteur en 21 parties et demi, une de ces parties sera le module. On en prendra 4 pour l'entablement et 17 et demi pour la colonne. Ce module sera divisé en 18 parties et pour les subdivisions chacune de ces parties en 18 minutes. Pour les détails on se reportera à la planche 49.




F. Esquié, del.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Ecoles - Paris.

Strasmann, Sc.

On ne connaît que très peu d'exemples d'ordre corinthien Grec. Celui que nous donnons dérive du monument connu sous le nom de Lysicrates à Athènes. Pour dessiner un entrecolonnement corinthien Grec, étant donné la hauteur on choisira cette dimension en 27 parties égales. Une de ces parties sera le module. On prendra alors 5 modules pour l'entablement et il en restera 22 pour la colonne, les colonnes s'espaceront de 9 modules et 1/2 d'axe en axe. Pour les détails on se reportera à la planche 51.



ÉTUDES DE PORTES

Fig. 1.





Fig. 2



Aus der Ecole Paris.




Fig. 1




Fig. 2

P. Esquisse de la


La figure 1 représente une porte destinée par Vignole au Palais de la Chancellerie et qui ne fut pas exécutée. On remarquera que la largeur égale sensiblement à la moitié de la hauteur. Le chambré est environ la huitième de la largeur de l'ouverture.

La fig. 2 représente la porte du Palais de Caprarolo et est aussi destinée à Vignole. La porte a sa hauteur le double de sa largeur; les pilastres ont huit dixièmes et l'entablement le quart de la hauteur des pilastres.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Écoles, Paris.

Streumann, Sc.

PORTE D'ENTRÉE DU PALAIS FARNÈSE À ROME




P. Esauit. del.

Comme exemple de porte circulaire
pas rendu compte dans notre dessin.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Ecoles — Paris.

Strasmann, Sc.




CHARLES SCHMID, ÉDITEUR, 61, Rue des Bonnes-Paroisses.

P. Biquini del.

Cette porte, fait partie du monument du Panthéon II est établie, que la portique précitant la rotonde et dont cette porte avec vantaux en bronze fait partie, a été construite au temps d'Appien.

Brasman, 20




CHARLES SCHMID, ÉDITEUR, 51, Rue des Beaux-Arts, Paris.


Dans la fig. 30-1 nous avons représenté la fenêtre du rez-de-chaussée du palais de Caprarola, la hauteur est le double de la largeur et la largeur est le double de la hauteur. Nous donnons fig. 2 un exemple de fenêtre d'ordre rustique élevée au rez-de-chaussée du bâtiment d'entrée de la Villa du Pape Jules II à Rome. La hauteur est aussi le double de la largeur.

Stramann, sc.

BASE TOSCANE



BASE DORIQUE




P. Enquêté del.

CHARLES SCHMID, EDITEUR 50, Rue des Fossés-Saints.

Strasbourg, 18.


Pour obtenir l'ombre des bases toscanes et doriques il faut couper ces bases par des plans verticaux parallèles aux rayons de lumière, on obtiendra ainsi des courbes de section à l'aide desquelles on pourra tracer point par point les limites d'ombre et de lumière en leur moment des tangentes à 45° et on les prolongera jusqu'à leur rencontre avec les courbes de section. Pour obtenir ces sections par des plans verticaux à 45° on sera obligé pour les surfaces courbes de considérer les rencontres de ces plans verticaux à 45° avec des sections des mêmes surfaces par des plans horizontaux. L'intersection de la figure sera d'ailleurs comprise la trace.

Projection verticale*Projection horizontale**F. Esquié, del.*

CHARLES SCHMID, ÉDITEUR, 51, Rue des Écoles — Paris.

Strasmann, Sc.

Pour obtenir les ombres du chapiteau on se sert du même procédé employé pour la base. C'est-à-dire en se servant de sections par une suite de plans verticaux coupant le chapiteau suivant le parallélisme du rayon lumineux. Nous avons donné outre les ombres propres du chapiteau, celles qui seraient portées par l'ensemble sur un plan vertical passant par l'axe.




P. Boqué, del.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Écoles — Paris.

Strasmann, Sc.

Même procédé que pour le chapiteau toscain. Le chapiteau surmonté de l'architrave porterait ombre d'après cette planche sur un plan vertical, parallèle au tableau et passant par l'axe de la colonne.



P. Esquié, del.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Beaux-Arts, Paris.


Strasmann, Sc.

Sur cette planche nous avons indiqué les ombres du chapiteau Ionique vu de face et les ombres portées par l'ensemble sur un plan vertical parallèle au tableau et passant par l'axe de la colonne. La méthode employée pour obtenir les divers points de l'ombre est toujours la même.

ÉTUDE D'OMBRE DE LA BASE ET DU CHÂTEAU DE L'ORDRE IONIQUE VU DE PROFIL.

Projection verticale

Projection verticale



Projection horizontale

Module

Projection horizontale

Parties de

3 6 9 12 15 18 21 24 27 30 33 36 39 42 45 48 51 54 57 60 63 66 69 72 75 78 81 84 87 90 93 96 99 102 105 108 111 114 117 120 123 126 129 132 135 138 141 144 147 150 153 156 159 162 165 168 171 174 177 180 183 186 189 192 195 198 201 204 207 210 213 216 219 222 225 228 231 234 237 240 243 246 249 252 255 258 261 264 267 270 273 276 279 282 285 288 291 294 297 300 303 306 309 312 315 318 321 324 327 330 333 336 339 342 345 348 351 354 357 360 363 366 369 372 375 378 381 384 387 390 393 396 399 402 405 408 411 414 417 420 423 426 429 432 435 438 441 444 447 450 453 456 459 462 465 468 471 474 477 480 483 486 489 492 495 498 501 504 507 510 513 516 519 522 525 528 531 534 537 540 543 546 549 552 555 558 561 564 567 570 573 576 579 582 585 588 591 594 597 600 603 606 609 612 615 618 621 624 627 630 633 636 639 642 645 648 651 654 657 660 663 666 669 672 675 678 681 684 687 690 693 696 699 702 705 708 711 714 717 720 723 726 729 732 735 738 741 744 747 750 753 756 759 762 765 768 771 774 777 780 783 786 789 792 795 798 801 804 807 810 813 816 819 822 825 828 831 834 837 840 843 846 849 852 855 858 861 864 867 870 873 876 879 882 885 888 891 894 897 900 903 906 909 912 915 918 921 924 927 930 933 936 939 942 945 948 951 954 957 960 963 966 969 972 975 978 981 984 987 990 993 996 999 1002 1005 1008 1011 1014 1017 1020 1023 1026 1029 1032 1035 1038 1041 1044 1047 1050 1053 1056 1059 1062 1065 1068 1071 1074 1077 1080 1083 1086 1089 1092 1095 1098 1101 1104 1107 1110 1113 1116 1119 1122 1125 1128 1131 1134 1137 1140 1143 1146 1149 1152 1155 1158 1161 1164 1167 1170 1173 1176 1179 1182 1185 1188 1191 1194 1197 1200 1203 1206 1209 1212 1215 1218 1221 1224 1227 1230 1233 1236 1239 1242 1245 1248 1251 1254 1257 1260 1263 1266 1269 1272 1275 1278 1281 1284 1287 1290 1293 1296 1299 1302 1305 1308 1311 1314 1317 1320 1323 1326 1329 1332 1335 1338 1341 1344 1347 1350 1353 1356 1359 1362 1365 1368 1371 1374 1377 1380 1383 1386 1389 1392 1395 1398 1401 1404 1407 1410 1413 1416 1419 1422 1425 1428 1431 1434 1437 1440 1443 1446 1449 1452 1455 1458 1461 1464 1467 1470 1473 1476 1479 1482 1485 1488 1491 1494 1497 1500 1503 1506 1509 1512 1515 1518 1521 1524 1527 1530 1533 1536 1539 1542 1545 1548 1551 1554 1557 1560 1563 1566 1569 1572 1575 1578 1581 1584 1587 1590 1593 1596 1599 1602 1605 1608 1611 1614 1617 1620 1623 1626 1629 1632 1635 1638 1641 1644 1647 1650 1653 1656 1659 1662 1665 1668 1671 1674 1677 1680 1683 1686 1689 1692 1695 1698 1701 1704 1707 1710 1713 1716 1719 1722 1725 1728 1731 1734 1737 1740 1743 1746 1749 1752 1755 1758 1761 1764 1767 1770 1773 1776 1779 1782 1785 1788 1791 1794 1797 1800 1803 1806 1809 1812 1815 1818 1821 1824 1827 1830 1833 1836 1839 1842 1845 1848 1851 1854 1857 1860 1863 1866 1869 1872 1875 1878 1881 1884 1887 1890 1893 1896 1899 1902 1905 1908 1911 1914 1917 1920 1923 1926 1929 1932 1935 1938 1941 1944 1947 1950 1953 1956 1959 1962 1965 1968 1971 1974 1977 1980 1983 1986 1989 1992 1995 1998 2001 2004 2007 2010 2013 2016 2019 2022 2025 2028 2031 2034 2037 2040 2043 2046 2049 2052 2055 2058 2061 2064 2067 2070 2073 2076 2079 2082 2085 2088 2091 2094 2097 2100 2103 2106 2109 2112 2115 2118 2121 2124 2127 2130 2133 2136 2139 2142 2145 2148 2151 2154 2157 2160 2163 2166 2169 2172 2175 2178 2181 2184 2187 2190 2193 2196 2199 2202 2205 2208 2211 2214 2217 2220 2223 2226 2229 2232 2235 2238 2241 2244 2247 2250 2253 2256 2259 2262 2265 2268 2271 2274 2277 2280 2283 2286 2289 2292 2295 2298 2301 2304 2307 2310 2313 2316 2319 2322 2325 2328 2331 2334 2337 2340 2343 2346 2349 2352 2355 2358 2361 2364 2367 2370 2373 2376 2379 2382 2385 2388 2391 2394 2397 2400 2403 2406 2409 2412 2415 2418 2421 2424 2427 2430 2433 2436 2439 2442 2445 2448 2451 2454 2457 2460 2463 2466 2469 2472 2475 2478 2481 2484 2487 2490 2493 2496 2499 2502 2505 2508 2511 2514 2517 2520 2523 2526 2529 2532 2535 2538 2541 2544 2547 2550 2553 2556 2559 2562 2565 2568 2571 2574 2577 2580 2583 2586 2589 2592 2595 2598 2601 2604 2607 2610 2613 2616 2619 2622 2625 2628 2631 2634 2637 2640 2643 2646 2649 2652 2655 2658 2661 2664 2667 2670 2673 2676 2679 2682 2685 2688 2691 2694 2697 2700 2703 2706 2709 2712 2715 2718 2721 2724 2727 2730 2733 2736 2739 2742 2745 2748 2751 2754 2757 2760 2763 2766 2769 2772 2775 2778 2781 2784 2787 2790 2793 2796 2799 2802 2805 2808 2811 2814 2817 2820 2823 2826 2829 2832 2835 2838 2841 2844 2847 2850 2853 2856 2859 2862 2865 2868 2871 2874 2877 2880 2883 2886 2889 2892 2895 2898 2901 2904 2907 2910 2913 2916 2919 2922 2925 2928 2931 2934 2937 2940 2943 2946 2949 2952 2955 2958 2961 2964 2967 2970 2973 2976 2979 2982 2985 2988 2991 2994 2997 3000 3003 3006 3009 3012 3015 3018 3021 3024 3027 3030 3033 3036 3039 3042 3045 3048 3051 3054 3057 3060 3063 3066 3069 3072 3075 3078 3081 3084 3087 3090 3093 3096 3099 3102 3105 3108 3111 3114 3117 3120 3123 3126 3129 3132 3135 3138 3141 3144 3147 3150 3153 3156 3159 3162 3165 3168 3171 3174 3177 3180 3183 3186 3189 3192 3195 3198 3201 3204 3207 3210 3213 3216 3219 3222 3225 3228 3231 3234 3237 3240 3243 3246 3249 3252 3255 3258 3261 3264 3267 3270 3273 3276 3279 3282 3285 3288 3291 3294 3297 3300 3303 3306 3309 3312 3315 3318 3321 3324 3327 3330 3333 3336 3339 3342 3345 3348 3351 3354 3357 3360 3363 3366 3369 3372 3375 3378 3381 3384 3387 3390 3393 3396 3399 3402 3405 3408 3411 3414 3417 3420 3423 3426 3429 3432 3435 3438 3441 3444 3447 3450 3453 3456 3459 3462 3465 3468 3471 3474 3477 3480 3483 3486 3489 3492 3495 3498 3501 3504 3507 3510 3513 3516 3519 3522 3525 3528 3531 3534 3537 3540 3543 3546 3549 3552 3555 3558 3561 3564 3567 3570 3573 3576 3579 3582 3585 3588 3591 3594 3597 3600 3603 3606 3609 3612 3615 3618 3621 3624 3627 3630 3633 3636 3639 3642 3645 3648 3651 3654 3657 3660 3663 3666 3669 3672 3675 3678 3681 3684 3687 3690 3693 3696 3699 3702 3705 3708 3711 3714 3717 3720 3723 3726 3729 3732 3735 3738 3741 3744 3747 3750 3753 3756 3759 3762 3765 3768 3771 3774 3777 3780 3783 3786 3789 3792 3795 3798 3801 3804 3807 3810 3813 3816 3819 3822 3825 3828 3831 3834 3837 3840 3843 3846 3849 3852 3855 3858 3861 3864 3867 3870 3873 3876 3879 3882 3885 3888 3891 3894 3897 3900 3903 3906 3909 3912 3915 3918 3921 3924 3927 3930 3933 3936 3939 3942 3945 3948 3951 3954 3957 3960 3963 3966 3969 3972 3975 3978 3981 3984 3987 3990 3993 3996 3999 4002 4005 4008 4011 4014 4017 4020 4023 4026 4029 4032 4035 4038 4041 4044 4047 4050 4053 4056 4059 4062 4065 4068 4071 4074 4077 4080 4083 4086 4089 4092 4095 4098 4101 4104 4107 4110 4113 4116 4119 4122 4125 4128 4131 4134 4137 4140 4143 4146 4149 4152 4155 4158 4161 4164 4167 4170 4173 4176 4179 4182 4185 4188 4191 4194 4197 4200 4203 4206 4209 4212 4215 4218 4221 4224 4227 4230 4233 4236 4239 4242 4245 4248 4251 4254 4257 4260 4263 4266 4269 4272 4275 4278 4281 4284 4287 4290 4293 4296 4299 4302 4305 4308 4311 4314 4317 4320 4323 4326 4329 4332 4335 4338 4341 4344 4347 4350 4353 4356 4359 4362 4365 4368 4371 4374 4377 4380 4383 4386 4389 4392 4395 4398 4401 4404 4407 4410 4413 4416 4419 4422 4425 4428 4431 4434 4437 4440 4443 4446 4449 4452 4455 4458 4461 4464 4467 4470 4473 4476 4479 4482 4485 4488 4491 4494 4497 4500 4503 4506 4509 4512 4515 4518 4521 4524 4527 4530 4533 4536 4539 4542 4545 4548 4551 4554 4557 4560 4563 4566 4569 4572 4575 4578 4581 4584 4587 4590 4593 4596 4599 4602 4605 4608 4611 4614 4617 4620 4623 4626 4629 4632 4635 4638 4641 4644 4647 4650 4653 4656 4659 4662 4665 4668 4671 4674 4677 4680 4683 4686 4689 4692 4695 4698 4701 4704 4707 4710 4713 4716 4719 4722 4725 4728 4731 4734 4737 4740 4743 4746 4749 4752 4755 4758 4761 4764 4767 4770 4773 4776 4779 4782 4785 4788 4791 4794 4797 4800 4803 4806 4809 4812 4815 4818 4821 4824 4827 4830 4833 4836 4839 4842 4845 4848 4851 4854 4857 4860 4863 4866 4869 4872 4875 4878 4881 4884 4887 4890 4893 4896 4899 4902 4905 4908 4911 4914 4917 4920 4923 4926 4929 4932 4935 4938 4941 4944 4947 4950 4953 4956 4959 4962 4965 4968 4971 4974 4977 4980 4983 4986 4989 4992 4995 4998 5001 5004 5007 5010 5013 5016 5019 5022 5025 5028 5031 5034 5037 5040 5043 5046 5049 5052 5055 5058 5061 5064 5067 5070 5073 5076 5079 5082 5085 5088 5091 5094 5097 5100 5103 5106 5109 5112 5115 5118 5121 5124 5127 5130 5133 5136 5139 5142 5145 5148 5151 5154 5157 5160 5163 5166 5169 5172 5175 5178 5181 5184 5187 5190 5193 5196 5199 5202 5205 5208 5211 5214 5217 5220 5223 5226 5229 5232 5235 5238 5241 5244 5247 5250 5253 5256 5259 5262 5265 5268 5271 5274 5277 5280 5283 5286 5289 5292 5295 5298 5301 5304 5307 5310 5313 5316 5319 5322 5325 5328 5331 5334 5337 5340 5343 5346 5349 5352 5355 5358 5361 5364 5367 5370 5373 5376 5379 5382 5385 5388 5391 5394 5397 5400 5403 5406 5409 5412 5415 5418 5421 5424 5427 5430 5433 5436 5439 5442 5445 5448 5451 5454 5457 5460 5463 5466 5469 5472 5475 5478 5481 5484 5487 5490 5493 5496 5499 5502 5505 5508 5511 5514 5517 5520 5523 5526 5529 5532 5535 5538 5541 5544 5547 5550 5553 5556 5559 5562 5565 5568 5571 5574 5577 5580 5583 5586 5589 5592 5595 5598 5601 5604 5607 5610 5613 5616 5619 5622 5625 5628 5631 5634 5637 5640 5643 5646 5649 5652 5655 5658 5661 5664 5667 5670 5673 5676 5679 5682 5685 5688 5691 5694 5697 5700 5703 5706 5709 5712 5715 5718 5721 5724 5727 5730 5733 5736 5739 5742 5745 5748 5751 5754 5757 5760 5763 5766 5769 5772 5775 5778 5781 5784 5787 5790 5793 5796 5799 5802 5805 5808 5811 5814 5817 5820 5823 5826 5829 5832 5835 5838 5841 5844 5847 5850 5853 5856 5859 5862 5865 5868 5871 5874 5877 5880 5883 5886 5889 5892 5895 5898 5901 5904 5907 5910 5913 5916 5919 5922 5925 5928 5931 5934 5937 5940 5943 5946 5949 5952 5955 5958 5961 5964 5967 5970 5973 5976 5979 5982 5985 5988 5991 5994 5997 6000 6003 6006 6009 6012 6015 6018 6021 6024 6027 6030 6033 6036 6039 6042 6045 6048 6051 6054 6057 6060 6063 6066 6069 6072 6075 6078 6081 6084 6087 6090 6093 6096 6099 6102 6105 6108 6111 6114 6117 6120 6123 6126 6129 6132 6135 6138 6141 6144 6147 6150 6153 6156 6159 6162 6165 6168 6171 6174 6177 6180 6183 6186 6189 6192 6195 6198 6201 6204 6207 6210 6213 6216 6219 6222 6225 6228 6231 6234 6237 6240 6243 6246 6249 6252 6255 6258 6261 6264 6267 6270 6273 6276 6279 6282 6285 6288 6291 6294 6297 6300 6303 6306 6309 6312 6315 6318 6321 6324 6327 6330 6333 6336 6339 6342 6345 6348 6351 6354 6357 6360 6363 6366 6369 6372 6375 6378 6381 6384 6387 6390 6393 6396 6399 6402 6405 6408 6411 6414 6417 6420 6423 6426 6429 6432 6435 6438 6441 6444 6447 6450 6453 6456 6459 6462 6465 6468 6471 6474 6477 6480 6483 6486 6489 6492 6495 6498 6501 6504 6507 6510 6513 6516 6519 6522 6525 6528 6531 6534 6537 6540 6543 6546 6549 6552 6555 6558 6561 6564 6567 6570 6573 6576 6579 6582 6585 6588 6591 6594 6597 6600 6603 6606 6609 6612 6615 6618 6621 6624 6627 6630 6633 6636 6639 6642 6645 6648 6651 6654 6657 6660 6663 6666 6669 6672 6675 6678 6681 6684 6687 6690 6693 6696 6699 6702 6705 6708 6711 6714 6717 6720 6723 6726 6729 6732 6735 6738 6741 6744 6747 6750 6753 6756 6759 6762 6765 6768 6771 6774 6777 6780 6783 6786 6789 6792 6795 6798 6801 6804 6807 6810 6813 6816 6819 6822 6825 6828 6831 6834 6837 6840 6843 6846 6849 6852 6855 6858 6861 6864 6867 6870 6873 6876 6879 6882 6885 6888 6891 6894 6897 6900 6903 6906 6909 6912 6915 6918 6921 6924 6927 6930 6933 6936 6939 6942 6945 6948 6951 6954 6957 6960 6963 6966 6969 6972 6975 6978 6981 6984 6987 6990 6993 6996 6999 7002 7005 7008 7011 7014 7017 7020 7023 7026 7029 7032 7035 7038 7041 7044 7047 7050 7053 7056 7059 7062 7065 7068 7071 7074 7077 7080 7083 7086 7089 7092 7095 7098 7101 7104 7107 7110 7113 7116 7119 7122 7125 7128 7131 7134 7137 7140 7143 7146 7149 7152 7155 7158 7161 7164 7167 7170 7173 7176 7179 7182 7185 7188 7191 7194 7197 7200 7203 7206 7209 7212 7215 7218 7221 7224 7227 7230 7233 7236 7239 7242 7245 7248 7251 7254 7257 7260 7263 7266 7269 7272 7275 7278 7281 7284 7287 7290 7293 7296 7299 7302 7305 7308 7311 7314 7317 7320 7323 7326 7329 7332 7335 7338 7341 7344 7347 7350 7353 7356 7359 7362 7365


Fig. 1^{ère}

Fig. 2




Fig. 1 Ombres du tailloir et du vase du
chapiteau corinthien
Fig. 2 Ombres complètes du chapiteau
d'ordre corinthien

F. Exquis del.

On obtient l'ombre de la figure 1 en faisant une série de sections par des plans courbes parallèles à la direction de la lumière. Pour la figure 2 il faut d'abord isolément l'ombre de chacun de chacun des ornements du chapiteau (cf. d'après
à la construction exacte de l'ombre générale. Nous n'en donnons ici que le résultat, final.

CHARLES SCHMID, EDITEUR, 50, Rue des Écoles, Paris.

Stammann, sc.

Fig. 2

Pour déterminer les ombres portées par la corniche on trace d'abord les lignes AC et BD puis les lignes horizontales CE', D'G' puis en menant des lignes à 45° par les points EF G on obtiendra les points E' F' G'.

Pour tracer l'ombre du fronton on déterminera d'abord les lignes MP, ON, RS, XY on fera ensuite des sections par des plans verticaux parallèles aux rayons lumineux, on obtiendra en suite les limites d'ombres en procédant comme pour la corniche.

Pour la fig. 2 la précision est la même, on aura seulement à chercher un plus grand nombre de points pour obtenir les courbes.








Fig. 1

Fig. 1 Etude des ombres portées d'un fronton à modillons

Fig. 2 Etude des ombres d'une corniche d'ordre corinthien



On obtient les ombres portées de ce portique en menant des lignes à 45° par tous les points pouvant porter ombre que l'on veut, dans le plan aux plans sur lesquels les ombres doivent se projeter. De ces points on élève des verticales jusqu'aux intersections avec les lignes à 45° tirées des points correspondants de l'élévation déterminant les points extrêmes des ombres à obtenir. Pour le détail des ombres portées par les chapiteaux on se reportera au détail suivant.




P. Esquié, del.

CHARLES SCHMID, EDITEUR, 51, Rue des Ecoles, Paris.

Strammann, sc.

On nomme planchers des pans de charpente qui se placent horizontalement pour séparer les différents étages d'une construction et en supporter les aires ou parquets, les planchers se composent de 3 parties 1^{re} le pleynd, 2^e la charpente proprement dite 3^e le revêtement ou parquet, lorsque la pièce est de petite dimension, on n'emploie que les solives, que l'on espace généralement de 0,33 d'axe en axe. Lorsque l'espace est plus considérable, on fait porter les solives par des pièces plus fortes, qui portent le nom de poutres. Elles doivent avoir au moins 0,25 de prise dans le mur, les dimensions des bois sont proportionnées aux charges à supporter - pour la bonne conservation des bois il faut les isoler autant que possible des maçonneries et les enfermer le moins possible. Nous donnons deux exemples de planchers avec les dispositions principales que l'on peut rencontrer.




CHARLES SCHMID, ÉDITEUR, 51 Rue des Écoles, Paris

J. Trommann, sc.

P. Esquié, del.

Les pans de bois avec une stabilité maîtresse sont employés pour remplacer les murs. Les pans de bois intérieurs ne diffèrent de ceux extérieurs que par l'épaisseur qui est plus faible pour les intérieurs. Pour un pan de bois de 4^m00 de hauteur on donne 0,25^e aux poteaux corniers, 0,15 à ceux d' huisserie et de 0,10 à 0,22 à ceux de remplissage — lorsque les pans de bois s'élèvent de 3 à 4 étages les poteaux corniers ont de 0,25 à 0,30 et les sablières de 0,20 à 0,25 — le pan de bois est rempli soit par des lames de bois, soit par des briques s'il doit être apparent, soit par des plâtres maintenus par des lattes s'il doit être enduit. Le mûrier est de laisser les bois apparents.



P. Esquieu, del.

CHARLES SCHMID, ÉDITEUR, 54, Rue des Ecoles Paris.

Struemanus, sc.

On nomme comble la partie située au-dessus d'un édifice et sur laquelle on applique la couverture destinée à la garantir contre les intempéries des saisons. Pour porter cette couverture il faut établir de distance en distance (tous les 4 à 5 mètres environ) des assemblages de bois ou de fer que l'on nomme Fermes. Les dispositions de ces fermes varient suivant les besoins, les matériaux employés pour la couverture et le climat. Nous donnons ici trois exemples pour combles droits.

Fig. 1. 2. 3. Tracés divers de combles à la Mansard avec entrail inférieur.

Fig. 4. Combles à la Mansard sans entrail inférieur.

Fig. 1.

a tirant
b jambe de force
c entrail
d poutre
e arbalétrier
f aiselière
g jambette
h pannes de brisis
i faîtage
l sablière
m coyaux
n charpignolle




Fig. 2.

Fig. 3.


Fig. 4.

P. Erquié, del.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Ecoles, Paris

Strosmann, sc.

Les fermes à la Mansard se composent comme les autres fermes, en général, de 2 à 6 mètres. Lorsque les combles types Fig. 1. 2. 3 doivent servir à l'habitation, on supprime les arbalétriers, et l'on remplace par des équerres en fer. Le tirant se reçoit alors une série de pièces de bois espacées de 0,53 d'axe en axe et d'un écartement de 0,17 et 0,09, sur lesquelles sont clouées les lattes destinées à recevoir l'enduit en plâtre.












P. Esquissé del.

CHARLES SCHMID, ÉDITEUR, 51, Rue des Écoles, Paris.

Strassmann. sc.

Quand les combles ne se terminent pas par des pignons on établit à leur place des pans de bois inclinés. Les pannes triangulaires en charpente placées aux extrémités d'un comble portent le nom de croupes. Si les murs sont à angle droit la croupe est dite droite. Si les murs ne sont pas ainsi disposés la croupe est dite biaise.



a. bâlis de dormant.
a' traverse de dormant.

b battants de noir contre dormant.
b' battants meneaux.

e traverse du haut.

f petits bois.

la paimelle.

F. GENTILE,

SCHMID, ÉDITEUR, 52, Rue des Écoles, Paris.

... de dimensions suffisantes pour s'oppos

[illegible]

der Welt.

es de charmante. 3 serrure.

h. paumelle.

1. The first step in the process is to identify the problem or issue that needs to be addressed. This involves gathering information and understanding the context of the problem.

ments, le problème à résoudre par la méthode des éléments finis est de trouver la solution de l'équation de Poisson

et les consonnes à leur tour, et les voyelles combinées de manière à ce que les variations

P. Franqui del

Fig. 1




Fig. 2




Fig. 3




Fig. 1 Voûte en berceau.
 Fig. 2 Voûte en arc de cloître.
 Fig. 3 Voûte en arc de cloître
 vue de par le haut.

l'Esquisse del
 la Fig. 1 représente une voûte en berceau droite avec son appareil en pierre. Ici, fig. 2 et 3 représentent deux voûtes dîtes en arc de cloître c'est à dire, formées par l'intersection de deux berceaux, ces deux berceaux pour
 avoir été semblables ce qui simplifie la disposition. Lorsque l'on veut faire pénétrer la lumière par la partie supérieure on emploie la disposition de la fig. 3.

CHARLES SCHMID, ÉDITEUR, 51, rue des Écoles, Paris.


Fig. 1 *Voûte d'arête barlongue*Fig. 2 *Voûte d'arête à double arête
avec pendatif*Fig. 3 *Voûte d'arête à double arête
et à pans coupés*

Fig. 3




Fig. 2




Fig. 1




Fig. 2




Fig. 1 Voûte sur pendentif avec
trumeaux, lunettes et arcs
doubleaux.

Fig. 2 Voûte sur pendentif avec
lunettes.




Fig. 1. Coupe suivant un plan parallèle aux génératrices du berceau.

Fig. 2. Coupe suivant un plan perpendiculaire aux génératrices du berceau.

Fig. 3. Développement de la moitié de la Voûte.

Fig. 4. Coupe suivant un plan parallèle aux génératrices du berceau.

Fig. 5. Coupe suivant un plan perpendiculaire aux génératrices du berceau.

Fig. 6. Développement de la moitié de la Voûte.




Fig. 7. Coupe d'une Coupole avec caissons.

Fig. 8. Plan d'un quart de la Coupole et des caissons.

Fig. 9. Développement d'un fuseau de la Coupole pour le tracé des caissons.

F. Bequès, del.

CHARLES SCHMID, ÉDITEUR, 55, Rue des Écoles, Paris

Strassmann, sc

Les caissons sont des compartiments creux, formés sur la surface d'une voûte afin d'en diminuer le poids tout en conservant la solidité désirée, les caissons sont susceptibles d'affirmer un degré de richesse approprié à l'édifice à décorer, soit par leur forme soit par les ornements qui seront appliqués. Nous donnons ici quelques exemples. Pour tracer les caissons en projection il faut pour les berceaux développer une portion de voûte suffisante pour avoir tous les éléments de la décoration. On reportera ensuite toutes les parties aux moyens des génératrices de la surface. Pour les coupôles on ne peut exactement développer la surface, on ne peut donc opérer que par approximation, en développant un fuseau que l'on prendra le plus petit possible.

卷之四



T3-BXH-134